

**Alabama Department of Transportation
Proposal Item Summary**

016. STPAA-0041(524)

MONROE COUNTY

Contract Time: December 31, 2024 Completion Date

DBE Goal Percent: 3.00

for constructing the Micro-Milling, Resurfacing, and Traffic Stripe on SR-41 from the Flat Creek Bridge (MP 55.963) to the junction of Tin Cup Alley (MP 62.500) northwest of Monroeville. Length 6.536 mi.

The Bracket Estimate on this project is from \$1,947,166 to \$2,379,869.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$5.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206E008	16	Each	Removing Guardrail End Anchor (All Type)
212A000	671	STA	Machine Grading Shoulders
405A000	5,809	Gal	Tack Coat
408B000	106,972	SQYD	Micro-Milling Existing Pavement (Approximately 0.00" Thru 1.00" Thick)
410H000	1	Each	Material Remixing Device
424A341	8,946	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
424A350	250	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
424B639	200	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
424B642	300	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
428A001	13	Mile	Scoring Bituminous Pavement Surface
430B043	450	Ton	Aggregate Surfacing (1" Down, Crusher Run)
433A000	96,798	SQYD	Scrub Seal
600A000	1	LS	Mobilization
630A001	100	LF	Steel Beam Guardrail, Class A, Type 2
630C079	8	Each	Guardrail End Anchor, Type 13 (MASH)
630C080	8	Each	Guardrail End Anchor, Type 20 Series (MASH)
650A000	500	CUYD	Topsoil
652A100	8	Acre	Seeding
652C000	50	Acre	Mowing
656A010	8	Acre	Mulching
665Q002	300	LF	Wattle
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 104,000.00)
701A227	13	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	12	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	2	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701C000	5	Mile	Broken Temporary Traffic Stripe
701C001	96	Mile	Solid Temporary Traffic Stripe
701G146	2,028	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G150	205	LF	Broken Yellow, Class W, Type A Traffic Stripe (5" Wide)
701G154	1,823	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
701H002	3,851	LF	Solid Traffic Stripe Removed (Tape)
701H007	205	LF	Broken Traffic Stripe Removed (Tape)
703A002	24	SQFT	Traffic Control Markings, Class 2, Type A
703D001	48	SQFT	Temporary Traffic Control Markings
705A030	1,202	Each	Pavement Markers, Class A-H, Type 2-C
705A032	61	Each	Pavement Markers, Class A-H, Type 1-B

Item No.	Quantity	Units	Description
705A037	746	Each	Pavement Markers, Class A-H, Type 2-D
740B000	1,296	SQFT	Construction Signs
740D000	50	Each	Channelizing Drums
740E000	100	Each	Cones (36 Inches High)
740M001	100	Each	Ballast For Cone
740O000	1	Each	Pilot Car