

**Alabama Department of Transportation  
Proposal Item Summary**

**017. STPAA-0184(502)**

**COLBERT COUNTY**

Contract Time: 45 Working Days

DBE Goal Percent: 2.00

for constructing the Micro-Milling, Resurfacing, and Traffic Stripe on SR-184 from the junction of SR-2/SR-17/SR-20 (US-43/US-72/Woodward Avenue) in Muscle Shoals to 0.160 mile east of the junction of CR-61. Length 4.708 mi.

The Bracket Estimate on this project is from \$1,899,770 to \$2,321,941.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$4.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
405A000	15,402	Gal	Tack Coat
408B001	154,012	SQYD	Micro-Milling Existing Pavement (Approximately 1.10" Thru 2.00" Thick)
410H000	1	Each	Material Remixing Device
424A360	12,105	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424A369	602	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B655	500	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B657	500	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
430B042	667	Ton	Aggregate Surfacing (Crushed Aggregate Base, Type A)
600A000	1	LS	Mobilization
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 101,900.00)
701A227	11	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	11	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	10	Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701A244	1	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	2,162	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	20	Mile	Broken Temporary Traffic Stripe
701C001	43	Mile	Solid Temporary Traffic Stripe
703A002	2,820	SQFT	Traffic Control Markings, Class 2, Type A
703B002	354	SQFT	Traffic Control Legends, Class 2, Type A
703D001	948	SQFT	Temporary Traffic Control Markings
705A030	520	Each	Pavement Markers, Class A-H, Type 2-C
705A031	25	Each	Pavement Markers, Class A-H, Type 1-A
705A032	480	Each	Pavement Markers, Class A-H, Type 1-B
705A037	130	Each	Pavement Markers, Class A-H, Type 2-D
705A038	245	Each	Pavement Markers, Class A-H, Type 2-E
730H001	4,600	LF	Loop Wire
740B000	1,220	SQFT	Construction Signs
740D000	200	Each	Channelizing Drums
740E000	300	Each	Cones (36 Inches High)
740M001	300	Each	Ballast For Cone
741C010	2	Each	Portable Sequential Arrow And Chevron Sign Unit