

**Alabama Department of Transportation
Proposal Item Summary**

021. STPAA-HSIP-0017(591)

PICKENS COUNTY

Contract Time: 45 Working Days

DBE Goal Percent: 1.00

for constructing the Safety Widening, Micro-Milling, Resurfacing, and Traffic Stripe on SR-17 from the Aliceville City Limits to the junction of CR-5. Length 4.856 mi.

The Bracket Estimate on this project is from \$2,569,938 to \$3,141,036.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$9.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206C010	33	SQYD	Removing Concrete Driveway
209A000	6	Each	Mailbox Reset, Single
305B077	1,871	Ton	Crushed Aggregate, Section 825, For Miscellaneous Use
405A000	21,316	Gal	Tack Coat
408B001	71,443	SQYD	Micro-Milling Existing Pavement (Approximately 1.10" Thru 2.00" Thick)
410H000	1	Each	Material Remixing Device
410I000	1	Each	Smoothness Testing, Certified Inertial Profiler
424A356	4,518	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/8" Maximum Aggregate Size Mix, ESAL Range C/D
424A359	45	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 3/8" Maximum Aggregate Size Mix, ESAL Range C/D
424B002	5,728	Ton	Superpave Bituminous Concrete Upper Binder Layer, 1/2" Maximum Aggregate Size mix, ESAL Range C/D
424B657	134	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B662	5	Ton	Superpave Bituminous Concrete Upper Binder Layer, Widening, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B685	729	Ton	Superpave Bituminous Concrete Lower Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B687	1,302	Ton	Superpave Bituminous Concrete Lower Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B692	2,011	Ton	Superpave Bituminous Concrete Lower Binder Layer, Widening, 1" Maximum Aggregate Size Mix, ESAL Range C/D
428A001	15	Mile	Scoring Bituminous Pavement Surface
433A000	69,796	SQYD	Scrub Seal
600A000	1	LS	Mobilization
665J002	330	LF	Silt Fence
665O001	330	LF	Silt Fence Removal
665Q002	500	LF	Wattle
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 148,000.00)
701A227	10	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	4	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	5	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701C000	23	Mile	Broken Temporary Traffic Stripe
701C001	75	Mile	Solid Temporary Traffic Stripe
703A002	498	SQFT	Traffic Control Markings, Class 2, Type A
703D001	2,490	SQFT	Temporary Traffic Control Markings
705A032	149	Each	Pavement Markers, Class A-H, Type 1-B
705A037	230	Each	Pavement Markers, Class A-H, Type 2-D
740B000	1,472	SQFT	Construction Signs

Item No.	Quantity	Units	Description
740D000	50	Each	Channelizing Drums
740E000	50	Each	Cones (36 Inches High)
740M001	50	Each	Ballast For Cone
740O000	1	Each	Pilot Car