

**Alabama Department of Transportation  
Proposal Item Summary**

**022. STPAA-HSIP-0189(535)**

**COFFEE COUNTY**

Contract Time: 30 Working Days

for constructing the Safety Widening, Planing, Resurfacing, and Traffic Stripe on SR-189 from the junction of Reese Avenue to the junction of SR-12 (US-84) in Elba. Length 0.931 mi.

The Bracket Estimate on this project is from \$528,742 to \$646,241.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$6.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
212A000	98	STA	Machine Grading Shoulders
405A000	2,120	Gal	Tack Coat
408A052	20,190	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
410H000	1	Each	Material Remixing Device
424A341	1,990	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
424A350	50	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
424B640	50	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range A/B
424B648	378	Ton	Superpave Bituminous Concrete Upper Binder Layer, Widening, 1 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B700	50	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 3/8" Maximum Aggregate Size mix, ESAL Range A/B
428A001	2	Mile	Scoring Bituminous Pavement Surface
600A000	1	LS	Mobilization
650A000	723	CUYD	Topsoil
652A100	2	Acre	Seeding
652C000	9	Acre	Mowing
656A010	2	Acre	Mulching
659C002	600	SQYD	Erosion Control Product, Type S2
665A000	2	Acre	Temporary Seeding
665B001	6	Ton	Temporary Mulching
665G000	200	Each	Sand Bags
665J002	250	LF	Silt Fence
665O001	250	LF	Silt Fence Removal
665Q002	310	LF	Wattle
666A001	2	Acre	Pest Control Treatment
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 27,600.00)
701A227	2	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	2	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	1	Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701A244	1	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	1,010	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	2	Mile	Broken Temporary Traffic Stripe
701C001	8	Mile	Solid Temporary Traffic Stripe
701D007	1	Mile	Solid Traffic Stripe Removed (Paint)
701D008	1	Mile	Solid Traffic Stripe Removed (Plastic)
701D014	1	Mile	Broken Traffic Stripe Removed (Paint)
701D015	1	Mile	Broken Traffic Stripe Removed (Plastic)

<b>Item No.</b>	<b>Quantity</b>	<b>Units</b>	<b>Description</b>
703A002	4,055	SQFT	Traffic Control Markings, Class 2, Type A
703B002	337	SQFT	Traffic Control Legends, Class 2, Type A
703D001	1,070	SQFT	Temporary Traffic Control Markings
705A030	194	Each	Pavement Markers, Class A-H, Type 2-C
705A032	151	Each	Pavement Markers, Class A-H, Type 1-B
705A037	74	Each	Pavement Markers, Class A-H, Type 2-D
705A038	411	Each	Pavement Markers, Class A-H, Type 2-E
740B000	966	SQFT	Construction Signs
740C000	27	SQFT	Special Construction Signs
740E000	150	Each	Cones (36 Inches High)
740M001	150	Each	Ballast For Cone
740O000	1	Each	Pilot Car