

**Alabama Department of Transportation  
Proposal Item Summary**

**031. STPNU-FMGR-0144(503)**

**ST. AND CLAIR COUNTIES**

Contract Time: 30 Working Days

DBE Goal Percent: 1.00

for constructing the Resurfacing (Micro-Surfacing Seal Coat, Type II & III) and Traffic Stripe on SR-144 from the junction of SR-53 (US-231) to the junction of CR-26 (Main Street) in Ragland. Length 10.159 mi.

The Bracket Estimate on this project is from \$1,296,299 to \$1,584,366.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$3.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
206D001	50	LF	Removing Guardrail
206E008	4	Each	Removing Guardrail End Anchor (All Type)
210D001	40	CUYD	Borrow Excavation (Loose Truckbed Measurement)
403B000	1,364	Ton	Micro-Surfacing Seal Coat, Type II
403B001	2,091	Ton	Micro-Surfacing Seal Coat, Type III
600A000	1	LS	Mobilization
630A001	25	LF	Steel Beam Guardrail, Class A, Type 2
630C080	4	Each	Guardrail End Anchor, Type 20 Series (MASH)
650A000	16	CUYD	Topsoil
654A001	60	SQYD	Solid Sodding (Bermuda)
665J002	100	LF	Silt Fence
665O001	100	LF	Silt Fence Removal
665Q002	100	LF	Wattle
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 76,000.00)
701A227	21	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	13	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	7	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	544	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	13	Mile	Broken Temporary Traffic Stripe
701C001	67	Mile	Solid Temporary Traffic Stripe
701G251	300	LF	Solid White, Class 2, Type A Traffic Stripe (6" Wide) (Rumble Strip)
703A002	1,068	SQFT	Traffic Control Markings, Class 2, Type A
703B002	282	SQFT	Traffic Control Legends, Class 2, Type A
703D001	96	SQFT	Temporary Traffic Control Markings
705A031	30	Each	Pavement Markers, Class A-H, Type 1-A
705A032	1,153	Each	Pavement Markers, Class A-H, Type 1-B
705A037	797	Each	Pavement Markers, Class A-H, Type 2-D
705A038	291	Each	Pavement Markers, Class A-H, Type 2-E
710A160	9	SQFT	Class 10 Aluminum Flat Sign Panels 0.08" Thick (Type XI Background)
710B021	13	LF	Roadway Sign Post (#3 U Channel, Galvanized Steel or 2", 14 Ga Square Tubular Steel)
740B000	791	SQFT	Construction Signs
740E000	100	Each	Cones (36 Inches High)
740M001	100	Each	Ballast For Cone
740O000	1	Each	Pilot Car