

**Alabama Department of Transportation
Proposal Item Summary**

037. RACR-009-015-004

CHAMBERS COUNTY

Contract Time: 120 Working Days

DBE Goal Percent: 2.00

for constructing the Roadway Improvements/Concrete Paving Project (Grading, Drainage, and Pavement) on SR-15 (US-29) from the South Exit Ramps (MP 209.851) over I-85 to the North Exit Ramps (MP 210.040) near the Georgia State Line. Length 0.236 mi.

The Bracket Estimate on this project is from \$4,686,848 to \$5,667,259.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$35.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206C008	504	SQYD	Removing Concrete Median
206D001	456	LF	Removing Guardrail
206D002	2,207	LF	Removing Curb
206D003	1,571	LF	Removing Curb And Gutter
206D016	460	LF	Removing Existing Bridge Handrail
206E001	4	Each	Removing Inlets
206E005	48	Each	Removing Concrete Posts
206E008	4	Each	Removing Guardrail End Anchor (All Type)
206E050	1	Each	Removing Slope Paved Headwall
206E062	12	Each	Removing Tree (19 - 36 Inch)
210A000	9,308	CUYD	Unclassified Excavation
210D000	22	CUYD	Borrow Excavation
214A000	141	CUYD	Structure Excavation
214B001	42	CUYD	Foundation Backfill, Commercial
301A004	18,398	SQYD	Crushed Aggregate Base Course, Type B, Plant Mixed, 4" Compacted Thickness
450A004	17,389	SQYD	Plain Cement Concrete Pavement, 9 Inches Thick
490A000	1,953	SQYD	Blast Cleaning
490B003	1,953	SQYD	Bridge Deck Overlay
490D000	352	SQFT	Bridge Deck Spall Repair
530A001	34	LF	18" Roadway Pipe (Class 3 R.C.)
530A002	129	LF	24" Roadway Pipe (Class 3 R.C.)
534E001	464	LF	Cleaning Existing Pipe (Less Than Or Equal To 48" Horizontal Opening)
600A000	1	LS	Mobilization
610D003	1,480	SQYD	Filter Blanket, Geotextile
618B003	297	SQYD	Concrete Driveway, 6" Thick (Includes Wire Mesh)
619A003	1	Each	24" Roadway Pipe End Treatment, Class 1
621A011	2	Each	Junction Boxes, Type 1 Or 1P
621C015	3	Each	Inlets, Type S1 Or S3 (1 Wing)
621C017	2	Each	Inlets, Type S1 Or S3 (2 Wing)
621D015	1	Each	Inlet Units, Type S1 Or S3
623A001	139	LF	Concrete Gutter (Valley)
623C000	1,573	LF	Combination Curb & Gutter, Type C
629E015	530	LF	Bridge Rail Retrofit, Type SC(CB)
630A001	325	LF	Steel Beam Guardrail, Class A, Type 2
630C077	3	Each	Guardrail End Anchor, Type 8 (MASH)
630C079	4	Each	Guardrail End Anchor, Type 13 (MASH)
630C080	1	Each	Guardrail End Anchor, Type 20 Series (MASH)
634E000	520	LF	Industrial Fence, 6 Feet High, Special Mounting

Item No.	Quantity	Units	Description
650A000	392	CUYD	Topsoil
650B000	88	CUYD	Topsoil From Stockpiles
654A000	643	SQYD	Solid Sodding
659C000	2,224	SQYD	Erosion Control Product, Type S4
665A000	5	Acre	Temporary Seeding
665B001	15	Ton	Temporary Mulching
665E000	150	SQYD	Polyethylene
665F000	200	Each	Hay Bales
665G000	200	Each	Sand Bags
665J002	3,500	LF	Silt Fence
665N000	600	Ton	Temporary Coarse Aggregate,ALDOT Number 1
665N001	150	Ton	Temporary Coarse Aggregate,ALDOT Number 4
665O001	3,500	LF	Silt Fence Removal
665P005	10	Each	Inlet Protection, Stage 3 Or 4
665Q002	460	LF	Wattle
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 338,700.00)
701B027	1,496	LF	Dotted, Class W, Type A Traffic Stripe (5" Wide)
701C000	1	Mile	Broken Temporary Traffic Stripe
701C001	1	Mile	Solid Temporary Traffic Stripe
701E003	1,064	LF	Solid Temporary Traffic Stripe (Tape)
701E013	532	LF	Broken Temporary Traffic Stripe (Tape)
701G142	2,240	LF	Broken White, Class W, Type A Traffic Stripe (5" Wide)
701G146	3,588	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G150	524	LF	Broken Yellow, Class W, Type A Traffic Stripe (5" Wide)
701G154	2,150	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
701G161	1,826	LF	Broken Black, Class W, Type B Traffic Stripe (5" Wide)
701H000	5,122	LF	Solid Traffic Stripe Removed (Paint)
701H002	1,064	LF	Solid Traffic Stripe Removed (Tape)
701H005	4,589	LF	Broken Traffic Stripe Removed (Paint)
701H007	532	LF	Broken Traffic Stripe Removed (Tape)
701H010	1,496	LF	Dotted Traffic Stripe Removed (Paint)
703A011	8,937	SQFT	Traffic Control Markings, Class W, Type A
703B011	90	SQFT	Traffic Control Legends, Class W, Type A
703D001	227	SQFT	Temporary Traffic Control Markings
705A011	177	Each	Pavement Markers, Class C, Type 1-A
705A012	100	Each	Pavement Markers, Class C, Type 1-B
705A030	78	Each	Pavement Markers, Class A-H, Type 2-C
705A031	177	Each	Pavement Markers, Class A-H, Type 1-A
705A032	100	Each	Pavement Markers, Class A-H, Type 1-B
705A037	133	Each	Pavement Markers, Class A-H, Type 2-D
705A038	618	Each	Pavement Markers, Class A-H, Type 2-E
709A001	1	Each	Milepost, Type B
710A160	36	SQFT	Class 10 Aluminum Flat Sign Panels 0.08" Thick (Type XI Background)
710A170	52	SQFT	Class 4, Aluminum Flat Sign Panels 0.08" Thick (Type IV Background)
710B021	378	LF	Roadway Sign Post (#3 U Channel, Galvanized Steel or 2", 14 Ga Square Tubular Steel)
720A070	3	Each	Vehicular Impact Attenuator Assembly (MASH) (Unidirectional,TL-2)
726A001	1,200	LF	Portable Concrete Safety Barriers, Type 6-A
740B000	2,564	SQFT	Construction Signs
740C000	48	SQFT	Special Construction Signs
740D000	200	Each	Channelizing Drums
740E000	200	Each	Cones (36 Inches High)
740F002	12	Each	Barricades, Type III
740M001	200	Each	Ballast For Cone
741C010	2	Each	Portable Sequential Arrow And Chevron Sign Unit

Item No.	Quantity	Units	Description
742A001	4	Each	Portable Changeable Message Sign, Type 2
742A003	4	Each	Portable Changeable Message Sign, Type 3