

**Alabama Department of Transportation
Proposal Item Summary**

014. NH-0001(631)

RUSSELL COUNTY

Contract Time: 65 Working Days

DBE Goal Percent: 0.50

for constructing the Planing, Resurfacing, and Traffic Stripe on SR-1 (US-431) from the junction of Old Seale Highway (MP 95.619) to the junction of Magnolia Greene Highway (MP 101.378). Length 5.758 mi.

The Bracket Estimate on this project is from \$3,651,909 to \$4,463,444.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$6.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206D001	238	LF	Removing Guardrail
206E008	4	Each	Removing Guardrail End Anchor (All Type)
401B100	204,480	SQYD	Bituminous Treatment E (With Polymer Additive)
405A000	8,485	Gal	Tack Coat
408A052	207,334	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
410H000	1	Each	Material Remixing Device
424A280	23,320	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range E
424A289	1,120	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 1/2" Maximum Aggregate Size Mix, ESAL Range E
424B283	100	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1/2" Maximum Aggregate Size Mix, ESAL Range E
424B287	100	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range E
428A001	23	Mile	Scoring Bituminous Pavement Surface
430B043	100	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
630A001	263	LF	Steel Beam Guardrail, Class A, Type 2
630C080	4	Each	Guardrail End Anchor, Type 20 Series (MASH)
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 195,800.00)
701A227	14	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	12	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	12	Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701B207	16,801	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	35	Mile	Broken Temporary Traffic Stripe
701C001	76	Mile	Solid Temporary Traffic Stripe
701D007	1	Mile	Solid Traffic Stripe Removed (Paint)
701D008	1	Mile	Solid Traffic Stripe Removed (Plastic)
701D014	1	Mile	Broken Traffic Stripe Removed (Paint)
701D015	1	Mile	Broken Traffic Stripe Removed (Plastic)
701G142	360	LF	Broken White, Class W, Type A Traffic Stripe (5" Wide)
701G146	360	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G154	360	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
703A002	11,026	SQFT	Traffic Control Markings, Class 2, Type A
703B002	1,614	SQFT	Traffic Control Legends, Class 2, Type A
703D001	8,386	SQFT	Temporary Traffic Control Markings
705A030	1,970	Each	Pavement Markers, Class A-H, Type 2-C
705A037	36	Each	Pavement Markers, Class A-H, Type 2-D
740B000	3,006	SQFT	Construction Signs
740C000	9	SQFT	Special Construction Signs

Item No.	Quantity	Units	Description
740D000	200	Each	Channelizing Drums
740E000	200	Each	Cones (36 Inches High)
740M001	200	Each	Ballast For Cone
741C010	2	Each	Portable Sequential Arrow And Chevron Sign Unit
742A001	2	Each	Portable Changeable Message Sign, Type 2