

**Alabama Department of Transportation  
Proposal Item Summary**

**015. NH-0001(632)**

**MADISON COUNTY**

Contract Time: 65 Working Days

DBE Goal Percent: 8.00

for constructing the Micro-Milling, Resurfacing, and Traffic Stripe on SR-1 (US-231/US-431) from the junction of Walker Lane in Hazel Green to the Tennessee State Line. Length 6.209 mi.

The Bracket Estimate on this project is from \$3,281,954 to \$4,011,277.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$7.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
206D001	488	LF	Removing Guardrail
206E008	10	Each	Removing Guardrail End Anchor (All Type)
209A000	1	Each	Mailbox Reset, Single
405A000	25,592	Gal	Tack Coat
408B001	257,742	SQYD	Micro-Milling Existing Pavement (Approximately 1.10" Thru 2.00" Thick)
410H000	1	Each	Material Remixing Device
424A360	21,245	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424A369	727	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B655	500	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
428A001	22	Mile	Scoring Bituminous Pavement Surface
430B043	8,516	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
630A001	525	LF	Steel Beam Guardrail, Class A, Type 2
630C077	2	Each	Guardrail End Anchor, Type 8 (MASH)
630C079	6	Each	Guardrail End Anchor, Type 13 (MASH)
630C080	2	Each	Guardrail End Anchor, Type 20 Series (MASH)
665Q002	800	LF	Wattle
666A001	1	Acre	Pest Control Treatment
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 175,000.00)
701A227	15	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	13	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	13	Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701A244	3	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	11,416	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	30	Mile	Broken Temporary Traffic Stripe
701C001	54	Mile	Solid Temporary Traffic Stripe
701G142	581	LF	Broken White, Class W, Type A Traffic Stripe (5" Wide)
701G146	581	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G154	581	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
701H002	1,162	LF	Solid Traffic Stripe Removed (Tape)
701H007	581	LF	Broken Traffic Stripe Removed (Tape)
703A002	9,653	SQFT	Traffic Control Markings, Class 2, Type A
703B002	2,051	SQFT	Traffic Control Legends, Class 2, Type A
703D001	5,200	SQFT	Temporary Traffic Control Markings
703E001	1,064	SQFT	Temporary Traffic Control Legends
705A030	1,418	Each	Pavement Markers, Class A-H, Type 2-C
705A037	312	Each	Pavement Markers, Class A-H, Type 2-D

<b>Item No.</b>	<b>Quantity</b>	<b>Units</b>	<b>Description</b>
705A038	640	Each	Pavement Markers, Class A-H, Type 2-E
730H001	13,600	LF	Loop Wire
740B000	3,266	SQFT	Construction Signs
740D000	200	Each	Channelizing Drums
740E000	200	Each	Cones (36 Inches High)
740M001	200	Each	Ballast For Cone
741C010	2	Each	Portable Sequential Arrow And Chevron Sign Unit