

**Alabama Department of Transportation
Proposal Item Summary**

020. NH-0012(582)

CHOCTAW COUNTY

Contract Time: December 31, 2024 Completion Date

DBE Goal Percent: 1.00

for constructing the Micro-Milling, Resurfacing, and Traffic Stripe on SR-12 (US-84) from the Mississippi State Line to the intersection of SR-17 in Silas. Length 8.542 mi.

The Bracket Estimate on this project is from \$1,980,800 to \$2,420,978.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$5.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
212A000	903	STA	Machine Grading Shoulders
405A000	16,769	Gal	Tack Coat
408B001	167,686	SQYD	Micro-Milling Existing Pavement (Approximately 1.10" Thru 2.00" Thick)
410H000	1	Each	Material Remixing Device
424A360	11,517	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424A369	350	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B655	300	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B657	200	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
428A001	18	Mile	Scoring Bituminous Pavement Surface
430B043	400	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
650A000	500	CUYD	Topsoil
652A100	13	Acre	Seeding
652C000	32	Acre	Mowing
656A010	13	Acre	Mulching
665Q002	300	LF	Wattle
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 105,000.00)
701A227	18	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	9	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	7	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701C000	28	Mile	Broken Temporary Traffic Stripe
701C001	86	Mile	Solid Temporary Traffic Stripe
701G252	300	LF	Solid White, Class 2, Type A Traffic Stripe (5" Wide) (Rumble Strip)
703A002	520	SQFT	Traffic Control Markings, Class 2, Type A
703B002	152	SQFT	Traffic Control Legends, Class 2, Type A
703D001	1,560	SQFT	Temporary Traffic Control Markings
705A030	308	Each	Pavement Markers, Class A-H, Type 2-C
705A032	338	Each	Pavement Markers, Class A-H, Type 1-B
705A037	687	Each	Pavement Markers, Class A-H, Type 2-D
740B000	1,670	SQFT	Construction Signs
740E000	100	Each	Cones (36 Inches High)
740M001	100	Each	Ballast For Cone
740O000	1	Each	Pilot Car