

**Alabama Department of Transportation
Proposal Item Summary**

021. NH-0012(583)

CLARKE COUNTY

Contract Time: December 31, 2024 Completion Date

DBE Goal Percent: 1.50

for constructing the Micro-Milling, Resurfacing, and Traffic Stripe on SR-12 (US-84) from 0.340 mile west of the junction of CR-22 (MP 40.320) to the intersection of SR-295 (MP 543.061) in Grove Hill. Length 2.740 mi.

The Bracket Estimate on this project is from \$2,102,587 to \$2,569,829.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$8.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206E008	4	Each	Removing Guardrail End Anchor (All Type)
212A000	627	STA	Machine Grading Shoulders
405A000	14,819	Gal	Tack Coat
408B001	148,184	SQYD	Micro-Milling Existing Pavement (Approximately 1.10" Thru 2.00" Thick)
410H000	1	Each	Material Remixing Device
424A361	13,595	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424A370	484	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B655	200	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B658	500	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
428A001	13	Mile	Scoring Bituminous Pavement Surface
430B043	150	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
630A001	25	LF	Steel Beam Guardrail, Class A, Type 2
630C079	2	Each	Guardrail End Anchor, Type 13 (MASH)
630C080	2	Each	Guardrail End Anchor, Type 20 Series (MASH)
650A000	500	CUYD	Topsoil
652A100	8	Acre	Seeding
652C000	54	Acre	Mowing
656A010	8	Acre	Mulching
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 112,000.00)
701A227	8	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	7	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	6	Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701B207	7,130	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	22	Mile	Broken Temporary Traffic Stripe
701C001	57	Mile	Solid Temporary Traffic Stripe
701G142	552	LF	Broken White, Class W, Type A Traffic Stripe (5" Wide)
701G146	1,104	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G154	552	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
701H002	1,656	LF	Solid Traffic Stripe Removed (Tape)
701H007	552	LF	Broken Traffic Stripe Removed (Tape)
703A002	5,348	SQFT	Traffic Control Markings, Class 2, Type A
703A011	50	SQFT	Traffic Control Markings, Class W, Type A
703B002	695	SQFT	Traffic Control Legends, Class 2, Type A
703B011	68	SQFT	Traffic Control Legends, Class W, Type A
703C003	117	SQFT	Removal Of Existing Traffic Control Markings Or Legends (Tape)

Item No.	Quantity	Units	Description
703D001	536	SQFT	Temporary Traffic Control Markings
705A030	930	Each	Pavement Markers, Class A-H, Type 2-C
705A032	1,732	Each	Pavement Markers, Class A-H, Type 1-B
705A037	195	Each	Pavement Markers, Class A-H, Type 2-D
705A038	862	Each	Pavement Markers, Class A-H, Type 2-E
740B000	1,528	SQFT	Construction Signs
740D000	50	Each	Channelizing Drums
740E000	150	Each	Cones (36 Inches High)
740M001	150	Each	Ballast For Cone
741C010	2	Each	Portable Sequential Arrow And Chevron Sign Unit