

**Alabama Department of Transportation  
Proposal Item Summary**

**022. NH-0013(637)**

**TUSCALOOSA COUNTY**

Contract Time: 60 Working Days

DBE Goal Percent: 3.00

for constructing the Micro-Milling, Resurfacing (Scrub Seal), Guardrail Installation, and Traffic Stripe on SR-13 (US-43) from 0.270 mile south of the intersection of Northside Road to the Fayette County Line. Length 8.538 mi.

The Bracket Estimate on this project is from \$3,184,798 to \$3,892,531.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$7.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
206D001	188	LF	Removing Guardrail
206E008	10	Each	Removing Guardrail End Anchor (All Type)
209A000	6	Each	Mailbox Reset, Single
209A001	1	Each	Mailbox Reset, Double
209A002	1	Each	Mailbox Reset, Multiple
305B077	921	Ton	Crushed Aggregate, Section 825, For Miscellaneous Use
405A000	12,992	Gal	Tack Coat
408B000	150,111	SQYD	Micro-Milling Existing Pavement (Approximately 0.00" Thru 1.00" Thick)
408B001	593	SQYD	Micro-Milling Existing Pavement (Approximately 1.10" Thru 2.00" Thick)
410H000	1	Each	Material Remixing Device
424A360	16,341	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424A369	460	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B655	584	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
428A001	26	Mile	Scoring Bituminous Pavement Surface
433A000	140,507	SQYD	Scrub Seal
600A000	1	LS	Mobilization
630A001	438	LF	Steel Beam Guardrail, Class A, Type 2
630C079	4	Each	Guardrail End Anchor, Type 13 (MASH)
630C080	6	Each	Guardrail End Anchor, Type 20 Series (MASH)
631C010	913	LF	Guardrail Reset
665Q002	200	LF	Wattle
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 167,950.00)
701A227	18	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	11	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	6	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	284	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	22	Mile	Broken Temporary Traffic Stripe
701C001	95	Mile	Solid Temporary Traffic Stripe
703A002	3,018	SQFT	Traffic Control Markings, Class 2, Type A
703B002	270	SQFT	Traffic Control Legends, Class 2, Type A
703D001	2,635	SQFT	Temporary Traffic Control Markings
705A030	27	Each	Pavement Markers, Class A-H, Type 2-C
705A032	743	Each	Pavement Markers, Class A-H, Type 1-B
705A037	511	Each	Pavement Markers, Class A-H, Type 2-D
710A165	9	SQFT	Class 10 Aluminum Flat Sign Panels 0.08" Thick (Type XI Background, Fluorescent)
710A170	17	SQFT	Class 4, Aluminum Flat Sign Panels 0.08" Thick (Type IV Background)
710B021	28	LF	Roadway Sign Post (#3 U Channel, Galvanized Steel or 2", 14 Ga Square Tubular Steel)

<b>Item No.</b>	<b>Quantity</b>	<b>Units</b>	<b>Description</b>
730H001	2,842	LF	Loop Wire
730I001	115	LF	Loop Detector Lead-In-Cable
740B000	2,027	SQFT	Construction Signs
740D000	25	Each	Channelizing Drums
740O000	1	Each	Pilot Car
742A001	2	Each	Portable Changeable Message Sign, Type 2