

**Alabama Department of Transportation
Proposal Item Summary**

023. NH-0042(546)

BALDWIN COUNTY

Contract Time: December 31, 2024 Completion Date

DBE Goal Percent: 3.00

for constructing the Planing, Resurfacing, Bridge Rail Retrofit, and Traffic Stripe on SR-42 (US-98) from 0.460 mile south of the intersection of CR-32 to the junction of CR-11 in Barnwell. Length 3.034 mi.

The Bracket Estimate on this project is from \$989,630 to \$1,209,548.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$7.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206D001	200	LF	Removing Guardrail
206D002	20	LF	Removing Curb
206E008	8	Each	Removing Guardrail End Anchor (All Type)
212A000	2	STA	Machine Grading Shoulders
405A000	6,017	Gal	Tack Coat
408A052	60,168	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
410H000	1	Each	Material Remixing Device
424A360	4,821	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424A369	144	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B653	250	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B657	100	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
600A000	1	LS	Mobilization
629E015	66	LF	Bridge Rail Retrofit, Type SC(CB)
630A001	50	LF	Steel Beam Guardrail, Class A, Type 2
630C079	4	Each	Guardrail End Anchor, Type 13 (MASH)
630C080	4	Each	Guardrail End Anchor, Type 20 Series (MASH)
650A000	500	CUYD	Topsoil
652C000	6	Acre	Mowing
654A001	240	SQYD	Solid Sodding (Bermuda)
665J002	500	LF	Silt Fence
665O001	500	LF	Silt Fence Removal
665Q002	180	LF	Wattle
666A001	1	Acre	Pest Control Treatment
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 52,375.00)
701A227	7	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	2	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	3	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	175	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	12	Mile	Broken Temporary Traffic Stripe
701C001	32	Mile	Solid Temporary Traffic Stripe
701G146	66	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G150	33	LF	Broken Yellow, Class W, Type A Traffic Stripe (5" Wide)
701H002	66	LF	Solid Traffic Stripe Removed (Tape)
701H007	33	LF	Broken Traffic Stripe Removed (Tape)
703A002	797	SQFT	Traffic Control Markings, Class 2, Type A
703B002	23	SQFT	Traffic Control Legends, Class 2, Type A

Item No.	Quantity	Units	Description
703D001	342	SQFT	Temporary Traffic Control Markings
703E001	23	SQFT	Temporary Traffic Control Legends
705A030	30	Each	Pavement Markers, Class A-H, Type 2-C
705A032	170	Each	Pavement Markers, Class A-H, Type 1-B
705A037	200	Each	Pavement Markers, Class A-H, Type 2-D
705A038	78	Each	Pavement Markers, Class A-H, Type 2-E
740B000	791	SQFT	Construction Signs
740D000	25	Each	Channelizing Drums
740E000	50	Each	Cones (36 Inches High)
740M001	50	Each	Ballast For Cone
740O000	1	Each	Pilot Car