

**Alabama Department of Transportation  
Proposal Item Summary**

**028. STPAA-0007(561)**

**DEKALB COUNTY**

Contract Time: 40 Working Days

DBE Goal Percent: 8.00

for constructing the Micro-Milling, Resurfacing, and Traffic Stripe on SR-7 (US-11) from the Etowah County Line to the junction of Lykes Lane in Collinsville. Length 7.109 mi.

The Bracket Estimate on this project is from \$1,554,694 to \$1,900,181.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$5.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
206E008	4	Each	Removing Guardrail End Anchor (All Type)
206E039	3	Each	Removing Mailboxes (Including Reset With a New 2 Inch Metal Or 4 Inch Timber Post)
210D001	100	CUYD	Borrow Excavation (Loose Truckbed Measurement)
405A000	13,120	Gal	Tack Coat
408B001	119,623	SQYD	Micro-Milling Existing Pavement (Approximately 1.10" Thru 2.00" Thick)
410H000	1	Each	Material Remixing Device
424A360	8,856	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424A369	327	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B655	500	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
428A001	14	Mile	Scoring Bituminous Pavement Surface
430B043	3,461	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
630A001	100	LF	Steel Beam Guardrail, Class A, Type 2
630A004	134	LF	Steel Beam Guardrail, Class B, Type 2
630C080	4	Each	Guardrail End Anchor, Type 20 Series (MASH)
652A100	1	Acre	Seeding
656A010	1	Acre	Mulching
665J002	500	LF	Silt Fence
665O001	500	LF	Silt Fence Removal
665Q002	800	LF	Wattle
666A001	1	Acre	Pest Control Treatment
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 82,800.00)
701A227	15	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	9	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	4	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	560	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	8	Mile	Broken Temporary Traffic Stripe
701C001	46	Mile	Solid Temporary Traffic Stripe
701G146	134	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G154	134	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
701H002	268	LF	Solid Traffic Stripe Removed (Tape)
703A002	3,428	SQFT	Traffic Control Markings, Class 2, Type A
703B002	68	SQFT	Traffic Control Legends, Class 2, Type A
703D001	2,928	SQFT	Temporary Traffic Control Markings
705A030	73	Each	Pavement Markers, Class A-H, Type 2-C
705A032	160	Each	Pavement Markers, Class A-H, Type 1-B
705A037	689	Each	Pavement Markers, Class A-H, Type 2-D

<b>Item No.</b>	<b>Quantity</b>	<b>Units</b>	<b>Description</b>
730H001	1,300	LF	Loop Wire
740B000	2,281	SQFT	Construction Signs
740D000	200	Each	Channelizing Drums
740E000	200	Each	Cones (36 Inches High)
740M001	200	Each	Ballast For Cone
740O000	1	Each	Pilot Car
741C010	2	Each	Portable Sequential Arrow And Chevron Sign Unit