

**Alabama Department of Transportation
Proposal Item Summary**

030. STPAA-0025(568)

BIBB COUNTY

Contract Time: 35 Working Days

for constructing the Resurfacing (Micro-Surfacing Seal Coat, Type II & III) and Traffic Stripe on SR-25 from the Hale County Line to the junction of SR-5 southwest of Brent. Length 13.912 mi.

The Bracket Estimate on this project is from \$1,772,011 to \$2,165,971.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$6.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206E043	166	Each	Removing Raised Pavement Markers
209A000	3	Each	Mailbox Reset, Single
403B000	1,910	Ton	Micro-Surfacing Seal Coat, Type II
403B001	2,335	Ton	Micro-Surfacing Seal Coat, Type III
600A000	1	LS	Mobilization
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 93,300.00)
701A227	28	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	20	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	6	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701C000	12	Mile	Broken Temporary Traffic Stripe
701C001	96	Mile	Solid Temporary Traffic Stripe
701D005	48	Mile	Solid Traffic Stripe Removed
701D013	6	Mile	Broken Traffic Stripe Removed
701G252	275	LF	Solid White, Class 2, Type A Traffic Stripe (5" Wide) (Rumble Strip)
703B002	56	SQFT	Traffic Control Legends, Class 2, Type A
703C000	56	SQFT	Removal Of Existing Traffic Control Markings Or Legends (Paint)
705A032	211	Each	Pavement Markers, Class A-H, Type 1-B
705A037	1,244	Each	Pavement Markers, Class A-H, Type 2-D
705A039	166	Each	Pavement Markers, Class A-H, Type 2-A
740B000	884	SQFT	Construction Signs
740D000	100	Each	Channelizing Drums
740E000	250	Each	Cones (36 Inches High)
740M001	250	Each	Ballast For Cone
740O000	1	Each	Pilot Car