

**Alabama Department of Transportation
Proposal Item Summary**

031. STPAA-0041(525)

DALLAS COUNTY

Contract Time: 55 Working Days

DBE Goal Percent: 2.00

for constructing the Planing, Resurfacing, Bridge Guardrail Retrofit, and Traffic Stripe on SR-41 from the Wilcox County Line to the junction of SR-89 (MP 105.179). Length 8.936 mi.

The Bracket Estimate on this project is from \$2,372,740 to \$2,900,016.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$3.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206D001	975	LF	Removing Guardrail
206E008	22	Each	Removing Guardrail End Anchor (All Type)
401B101	127,300	SQYD	Bituminous Treatment F (With Polymer Additive)
405A000	10,550	Gal	Tack Coat
408A052	128,700	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
410H000	1	Each	Material Remixing Device
424A360	11,795	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424A369	110	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B655	800	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B657	1,185	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B659	1,030	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1" Maximum Aggregate Size Mix, ESAL Range C/D
428A001	18	Mile	Scoring Bituminous Pavement Surface
430B043	1,735	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
610D003	300	SQYD	Filter Blanket, Geotextile
629D003	4	Each	Bridge Guardrail Retrofit, Type SC
630A001	1,050	LF	Steel Beam Guardrail, Class A, Type 2
630C079	12	Each	Guardrail End Anchor, Type 13 (MASH)
630C080	10	Each	Guardrail End Anchor, Type 20 Series (MASH)
665G000	100	Each	Sand Bags
665J002	250	LF	Silt Fence
665O001	250	LF	Silt Fence Removal
665Q002	250	LF	Wattle
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 138,000.00)
701A227	17	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	9	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	7	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701C000	14	Mile	Broken Temporary Traffic Stripe
701C001	52	Mile	Solid Temporary Traffic Stripe
701G146	575	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G154	575	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
701H001	914	LF	Solid Traffic Stripe Removed (Plastic)
701H006	914	LF	Broken Traffic Stripe Removed (Plastic)
703A002	116	SQFT	Traffic Control Markings, Class 2, Type A

Item No.	Quantity	Units	Description
703D001	232	SQFT	Temporary Traffic Control Markings
705A032	250	Each	Pavement Markers, Class A-H, Type 1-B
705A037	600	Each	Pavement Markers, Class A-H, Type 2-D
705A039	48	Each	Pavement Markers, Class A-H, Type 2-A
740B000	1,208	SQFT	Construction Signs
740D000	100	Each	Channelizing Drums
740E000	300	Each	Cones (36 Inches High)
740M001	300	Each	Ballast For Cone
740O000	1	Each	Pilot Car