

**Alabama Department of Transportation  
Proposal Item Summary**

**034. STPAA-0069(572)**

**MARSHALL COUNTY**

Contract Time: 80 Working Days

DBE Goal Percent: 4.00

for constructing the Micro-Milling, Resurfacing, Guardrail Installation, and Traffic Stripe on SR-69 from the junction of Holbrook Drive northeast of Arab to the junction of Nuel Road in Guntersville. Length 4.999 mi.

The Bracket Estimate on this project is from \$5,030,219 to \$6,148,046.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$9.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
206D001	7,900	LF	Removing Guardrail
206E008	18	Each	Removing Guardrail End Anchor (All Type)
405A000	30,282	Gal	Tack Coat
408B001	221,392	SQYD	Micro-Milling Existing Pavement (Approximately 1.10" Thru 2.00" Thick)
410H000	1	Each	Material Remixing Device
410I000	1	Each	Smoothness Testing, Certified Inertial Profiler
420A015	5,854	Ton	Polymer Modified Open Graded Friction Course
420B000	19,157	Gal	Open Graded Friction Course Tack Coat
424A356	11,688	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/8" Maximum Aggregate Size Mix, ESAL Range C/D
424A359	425	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 3/8" Maximum Aggregate Size Mix, ESAL Range C/D
424B650	17,620	Ton	Superpave Bituminous Concrete Upper Binder Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B661	678	Ton	Superpave Bituminous Concrete Upper Binder Layer, Widening, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B685	3,000	Ton	Superpave Bituminous Concrete Lower Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
428A001	9	Mile	Scoring Bituminous Pavement Surface
430B043	3,301	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
610D003	200	SQYD	Filter Blanket, Geotextile
630A001	7,675	LF	Steel Beam Guardrail, Class A, Type 2
630C080	18	Each	Guardrail End Anchor, Type 20 Series (MASH)
665G000	200	Each	Sand Bags
665Q002	400	LF	Wattle
666A001	1	Acre	Pest Control Treatment
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 265,265.00)
701A227	11	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	10	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	10	Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701A244	3	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	3,996	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	43	Mile	Broken Temporary Traffic Stripe
701C001	67	Mile	Solid Temporary Traffic Stripe
703A002	5,118	SQFT	Traffic Control Markings, Class 2, Type A
703B002	404	SQFT	Traffic Control Legends, Class 2, Type A
703D001	1,224	SQFT	Temporary Traffic Control Markings
705A030	1,040	Each	Pavement Markers, Class A-H, Type 2-C
705A037	846	Each	Pavement Markers, Class A-H, Type 2-D

<b>Item No.</b>	<b>Quantity</b>	<b>Units</b>	<b>Description</b>
705A038	40	Each	Pavement Markers, Class A-H, Type 2-E
730H001	5,100	LF	Loop Wire
740B000	2,546	SQFT	Construction Signs
740D000	200	Each	Channelizing Drums
740E000	200	Each	Cones (36 Inches High)
740M001	200	Each	Ballast For Cone
740N000	114	Each	Tubular Marker
741C010	2	Each	Portable Sequential Arrow And Chevron Sign Unit