

**Alabama Department of Transportation
Proposal Item Summary**

036. STPAA-0178(501)

CLARKE COUNTY

Contract Time: December 31, 2024 Completion Date

DBE Goal Percent: 3.00

for constructing the Micro-Milling, Resurfacing, and Traffic Stripe on SR-178 from the junction of SR-13 (US-43) to the junction of CR-27 (West Main Street) in Fulton. Length 1.905 mi.

The Bracket Estimate on this project is from \$610,454 to \$746,111.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$6.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206E008	8	Each	Removing Guardrail End Anchor (All Type)
212A000	197	STA	Machine Grading Shoulders
405A000	3,727	Gal	Tack Coat
408B001	37,267	SQYD	Micro-Milling Existing Pavement (Approximately 1.10" Thru 2.00" Thick)
410H000	1	Each	Material Remixing Device
424A360	2,562	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424A369	75	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B655	200	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B657	200	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
428A001	4	Mile	Scoring Bituminous Pavement Surface
430B043	100	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
630A001	50	LF	Steel Beam Guardrail, Class A, Type 2
630C079	4	Each	Guardrail End Anchor, Type 13 (MASH)
630C080	4	Each	Guardrail End Anchor, Type 20 Series (MASH)
650A000	200	CUYD	Topsoil
652A100	3	Acre	Seeding
652C000	8	Acre	Mowing
656A010	3	Acre	Mulching
665Q002	150	LF	Wattle
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 31,785.00)
701A227	4	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	4	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	1	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701C000	3	Mile	Broken Temporary Traffic Stripe
701C001	24	Mile	Solid Temporary Traffic Stripe
701G146	440	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G154	440	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
701G252	600	LF	Solid White, Class 2, Type A Traffic Stripe (5" Wide) (Rumble Strip)
701H001	120	LF	Solid Traffic Stripe Removed (Plastic)
701H002	880	LF	Solid Traffic Stripe Removed (Tape)
703A002	745	SQFT	Traffic Control Markings, Class 2, Type A
703B002	136	SQFT	Traffic Control Legends, Class 2, Type A
703D001	504	SQFT	Temporary Traffic Control Markings
705A030	438	Each	Pavement Markers, Class A-H, Type 2-C
705A032	43	Each	Pavement Markers, Class A-H, Type 1-B

Item No.	Quantity	Units	Description
705A037	204	Each	Pavement Markers, Class A-H, Type 2-D
731A021	1	Each	Traffic Counting Units, Type R
731B000	1	Each	Pole for Mounting Traffic Detection Equipment
740B000	888	SQFT	Construction Signs
740D000	50	Each	Channelizing Drums
740E000	100	Each	Cones (36 Inches High)
740M001	100	Each	Ballast For Cone
740O000	1	Each	Pilot Car