

**Alabama Department of Transportation  
Proposal Item Summary**

**040. STPAA-HSIP-0049(516)**

**TALLAPOOSA COUNTY**

Contract Time: 55 Working Days

DBE Goal Percent: 1.50

for constructing the Safety Widening, Micro-Milling, Resurfacing (Scrub Seal), Bridge Guardrail Retrofit, and Traffic Stripe on SR-49 from the junction of CR-57 to the junction of SR-22 in New Site. Length 7.664 mi.

The Bracket Estimate on this project is from \$2,491,603 to \$3,045,293.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$3.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
206D001	16	LF	Removing Guardrail
206E008	16	Each	Removing Guardrail End Anchor (All Type)
209A000	35	Each	Mailbox Reset, Single
405A000	13,089	Gal	Tack Coat
408B000	3,211	SQYD	Micro-Milling Existing Pavement (Approximately 0.00" Thru 1.00" Thick)
408B001	1,071	SQYD	Micro-Milling Existing Pavement (Approximately 1.10" Thru 2.00" Thick)
410H000	1	Each	Material Remixing Device
424A340	12,182	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424A349	250	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B639	250	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
424B642	250	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B677	3,368	Ton	Superpave Bituminous Concrete Lower Binder Layer, Widening, 1" Maximum Aggregate Size Mix, ESAL Range A/B
428A001	16	Mile	Scoring Bituminous Pavement Surface
430B043	2,200	Ton	Aggregate Surfacing (1" Down, Crusher Run)
433A000	130,889	SQYD	Scrub Seal
600A000	1	LS	Mobilization
610D003	1,600	SQYD	Filter Blanket, Geotextile
629D003	8	Each	Bridge Guardrail Retrofit, Type SC
630A001	50	LF	Steel Beam Guardrail, Class A, Type 2
630C077	1	Each	Guardrail End Anchor, Type 8 (MASH)
630C079	8	Each	Guardrail End Anchor, Type 13 (MASH)
630C080	7	Each	Guardrail End Anchor, Type 20 Series (MASH)
665A000	8	Acre	Temporary Seeding
665B001	24	Ton	Temporary Mulching
665G000	150	Each	Sand Bags
665J002	500	LF	Silt Fence
665O001	500	LF	Silt Fence Removal
665Q002	2,400	LF	Wattle
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 146,000.00)
701A227	15	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	13	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	1	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B205	360	LF	Dotted, Class 2, Type A, Traffic Stripe
701C000	1	Mile	Broken Temporary Traffic Stripe
701C001	56	Mile	Solid Temporary Traffic Stripe

<b>Item No.</b>	<b>Quantity</b>	<b>Units</b>	<b>Description</b>
701G146	2,210	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G150	860	LF	Broken Yellow, Class W, Type A Traffic Stripe (5" Wide)
701G154	500	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
703A002	774	SQFT	Traffic Control Markings, Class 2, Type A
703B002	23	SQFT	Traffic Control Legends, Class 2, Type A
703D001	554	SQFT	Temporary Traffic Control Markings
705A037	1,015	Each	Pavement Markers, Class A-H, Type 2-D
740B000	1,340	SQFT	Construction Signs
740D000	50	Each	Channelizing Drums
740E000	50	Each	Cones (36 Inches High)
740M001	50	Each	Ballast For Cone
740O000	1	Each	Pilot Car