

**Alabama Department of Transportation  
Proposal Item Summary**

**041. STPAA-HSIP-0051(522)**

**DALE COUNTY**

Contract Time: 55 Working Days

DBE Goal Percent: 3.00

for constructing the Safety Widening, Micro-Milling, Resurfacing, and Traffic Stripe on SR-51 from the junction of SR-53 (US-231) southwest of Arton to the Barbour County Line. Length 5.792 mi.

The Bracket Estimate on this project is from \$2,113,853 to \$2,583,598.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$8.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
206C010	45	SQYD	Removing Concrete Driveway
206D001	88	LF	Removing Guardrail
206E008	4	Each	Removing Guardrail End Anchor (All Type)
209A000	5	Each	Mailbox Reset, Single
210D021	100	CUYD	Borrow Excavation (Loose Truckbed Measurement)(A4 or Better)
212A000	372	STA	Machine Grading Shoulders
305B077	100	Ton	Crushed Aggregate, Section 825, For Miscellaneous Use
405A000	23,374	Gal	Tack Coat
408B001	106,231	SQYD	Micro-Milling Existing Pavement (Approximately 1.10" Thru 2.00" Thick)
410H000	1	Each	Material Remixing Device
424A361	10,889	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424A370	531	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B655	100	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B663	1,447	Ton	Superpave Bituminous Concrete Upper Binder Layer, Widening, 1 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B701	100	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 3/8" Maximum Aggregate Size mix, ESAL Range C/D
428A001	8	Mile	Scoring Bituminous Pavement Surface
600A000	1	LS	Mobilization
630A001	88	LF	Steel Beam Guardrail, Class A, Type 2
630C080	4	Each	Guardrail End Anchor, Type 20 Series (MASH)
650A000	1,378	CUYD	Topsoil
652A100	5	Acre	Seeding
652C000	40	Acre	Mowing
656A010	5	Acre	Mulching
659C002	450	SQYD	Erosion Control Product, Type S2
665A000	15	Acre	Temporary Seeding
665B001	45	Ton	Temporary Mulching
665E000	500	SQYD	Polyethylene
665J002	1,000	LF	Silt Fence
665O001	1,000	LF	Silt Fence Removal
665P005	3	Each	Inlet Protection, Stage 3 Or 4
665Q002	640	LF	Wattle
666A001	15	Acre	Pest Control Treatment
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 111,475.00)
701A227	12	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	10	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)

Item No.	Quantity	Units	Description
701A244	2	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	301	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	4	Mile	Broken Temporary Traffic Stripe
701C001	44	Mile	Solid Temporary Traffic Stripe
701D007	1	Mile	Solid Traffic Stripe Removed (Paint)
701D008	1	Mile	Solid Traffic Stripe Removed (Plastic)
701D014	1	Mile	Broken Traffic Stripe Removed (Paint)
701D015	1	Mile	Broken Traffic Stripe Removed (Plastic)
701G146	280	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G154	195	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
701G252	300	LF	Solid White, Class 2, Type A Traffic Stripe (5" Wide) (Rumble Strip)
703A002	1,695	SQFT	Traffic Control Markings, Class 2, Type A
703B002	182	SQFT	Traffic Control Legends, Class 2, Type A
703D001	2,706	SQFT	Temporary Traffic Control Markings
703E001	273	SQFT	Temporary Traffic Control Legends
705A030	484	Each	Pavement Markers, Class A-H, Type 2-C
705A032	116	Each	Pavement Markers, Class A-H, Type 1-B
705A037	559	Each	Pavement Markers, Class A-H, Type 2-D
730H001	300	LF	Loop Wire
740B000	1,415	SQFT	Construction Signs
740C000	18	SQFT	Special Construction Signs
740E000	150	Each	Cones (36 Inches High)
740M001	150	Each	Ballast For Cone
740O000	1	Each	Pilot Car