

**Alabama Department of Transportation
Proposal Item Summary**

042. STPAA-HSIP-0187(502)

MARION COUNTY

Contract Time: 35 Working Days

DBE Goal Percent: 3.00

for constructing the Safety Widening, Micro-Milling, Resurfacing (Scrub Seal), and Traffic Stripe on SR-187 from the junction of SR-17 (US-43) northeast of Hamilton to the junction of CR-29. Length 4.258 mi.

The Bracket Estimate on this project is from \$1,953,768 to \$2,387,939.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$8.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206C010	57	SQYD	Removing Concrete Driveway
305B077	916	Ton	Crushed Aggregate, Section 825, For Miscellaneous Use
405A000	17,826	Gal	Tack Coat
408B001	67,604	SQYD	Micro-Milling Existing Pavement (Approximately 1.10" Thru 2.00" Thick)
410H000	1	Each	Material Remixing Device
410I000	1	Each	Smoothness Testing, Certified Inertial Profiler
424A336	3,999	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/8" Maximum Aggregate Size Mix, ESAL Range A/B
424A339	84	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 3/8" Maximum Aggregate Size Mix, ESAL Range A/B
424B634	5,100	Ton	Superpave Bituminous Concrete Upper Binder Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B647	189	Ton	Superpave Bituminous Concrete Upper Binder Layer, Widening, 1" Maximum Aggregate Size Mix, ESAL Range A/B
424B670	100	Ton	Superpave Bituminous Concrete Lower Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range A/B
424B677	890	Ton	Superpave Bituminous Concrete Lower Binder Layer, Widening, 1" Maximum Aggregate Size Mix, ESAL Range A/B
428A001	13	Mile	Scoring Bituminous Pavement Surface
433A000	67,747	SQYD	Scrub Seal
600A000	1	LS	Mobilization
665J002	660	LF	Silt Fence
665O001	660	LF	Silt Fence Removal
665Q002	500	LF	Wattle
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 101,615.00)
701A227	9	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	8	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	1	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701C000	5	Mile	Broken Temporary Traffic Stripe
701C001	80	Mile	Solid Temporary Traffic Stripe
703A002	422	SQFT	Traffic Control Markings, Class 2, Type A
703D002	1,265	SQFT	Temporary Traffic Control Markings (Paint)
705A032	59	Each	Pavement Markers, Class A-H, Type 1-B
705A037	457	Each	Pavement Markers, Class A-H, Type 2-D
740B000	1,484	SQFT	Construction Signs
740D000	25	Each	Channelizing Drums
740O000	1	Each	Pilot Car