

**Alabama Department of Transportation  
Proposal Item Summary**

---

**044. STPAA-NR13(909)**

**JEFFERSON AND SHELBY COUNTIES**

Contract Time: 90 Working Days

DBE Goal Percent: 0.50

for constructing the Safety Improvements (Curb Ramp Installations) on SR-3, SR-4, SR-5, SR-7, SR-25, SR-75, SR-79, SR-119, SR-149, SR-155, SR-261, SR-269, and SR-378 at various locations in the East Central Region (Birmingham Area) as indicated in the plans.

The Bracket Estimate on this project is from \$440,608 to \$538,520.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$15.00 per set.

*The Principal Items of work are approximately as follows:*

<b>Item No.</b>	<b>Quantity</b>	<b>Units</b>	<b>Description</b>
206C000	1,111	SQYD	Removing Concrete Sidewalk
206D003	1,398	LF	Removing Curb And Gutter
600A000	1	LS	Mobilization
618A000	575	SQYD	Concrete Sidewalk, 4" Thick
618C001	3,220	SQFT	Detectable Warning Surface
618D000	975	SQYD	Curb Ramp
623C000	195	LF	Combination Curb & Gutter, Type C
650A000	55	CUYD	Topsoil
654A001	219	SQYD	Solid Sodding (Bermuda)
674A000	750	LF	Construction Safety Fence
740B000	587	SQFT	Construction Signs
740D000	100	Each	Channelizing Drums
740E000	100	Each	Cones (36 Inches High)
740G000	8	Each	Barricades, Type I, (Portable, 24 Inches Wide)
740M001	100	Each	Ballast For Cone
741C010	1	Each	Portable Sequential Arrow And Chevron Sign Unit