

**Alabama Department of Transportation
Proposal Item Summary**

050. STPSU-1720(252)

COLBERT COUNTY

Contract Time: 45 Working Days

DBE Goal Percent: 0.50

for constructing the Planing, Resurfacing, and Traffic Stripe on CR-40 (River Road) from the junction of Brick School Road northeast of Muscle Shoals to the junction of Foster Mill Road and along CR-40 (Foster Mill Road) to the Lawrence County Line (Site 1) and on CR-48 (Lime Kiln Road) from the junction of CR-40 (River Road) to the junction of Lime Kiln Hollow Drive (Site 2). Length 7.266 mi.

The Bracket Estimate on this project is from \$1,435,754 to \$1,754,811.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$6.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
401A006	100,751	SQYD	Bituminous Treatment G
405A000	5,518	Gal	Tack Coat
408A052	15,185	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
424A340	7,909	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B642	800	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
430B047	3,785	Ton	Aggregate Surfacing (3/4" Down, Crusher Run)
600A000	1	LS	Mobilization
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 76,000.00)
701A231	13	Mile	Solid White, Class 2, Type A Traffic Stripe
701A235	10	Mile	Solid Yellow, Class 2, Type A Traffic Stripe
701A245	3	Mile	Broken Yellow, Class 2, Type A Traffic Stripe
701B205	55	LF	Dotted, Class 2, Type A, Traffic Stripe
701C000	6	Mile	Broken Temporary Traffic Stripe
701C001	20	Mile	Solid Temporary Traffic Stripe
701G251	575	LF	Solid White, Class 2, Type A Traffic Stripe (6" Wide) (Rumble Strip)
703A002	1,108	SQFT	Traffic Control Markings, Class 2, Type A
703B002	157	SQFT	Traffic Control Legends, Class 2, Type A
703D001	1,108	SQFT	Temporary Traffic Control Markings
703E001	45	SQFT	Temporary Traffic Control Legends
705A030	10	Each	Pavement Markers, Class A-H, Type 2-C
705A032	514	Each	Pavement Markers, Class A-H, Type 1-B
705A037	639	Each	Pavement Markers, Class A-H, Type 2-D
705A038	66	Each	Pavement Markers, Class A-H, Type 2-E
740B000	1,131	SQFT	Construction Signs
740O000	1	Each	Pilot Car