

**Alabama Department of Transportation
Proposal Item Summary**

053. ATRP2-38-2022-465

LAMAR COUNTY

Contract Time: 55 Working Days

for constructing the Drainage Improvements (Grading, Drainage, and Pavement), Driveway Replacement, and Sidewalk Installation on SR-118 (US-278/Main Street) from the junction of Elm Street to a point near Outfall Ditch in Sulligent. Length 0.069 mi.

The Bracket Estimate on this project is from \$447,058 to \$546,405.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$9.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206C000	50	SQYD	Removing Concrete Sidewalk
206C010	255	SQYD	Removing Concrete Driveway
206D000	322	LF	Removing Pipe
206D003	333	LF	Removing Curb And Gutter
206D005	400	LF	Removing Gutter
206E001	3	Each	Removing Inlets
206E002	1	Each	Removing Junction Boxes
206E042	1	Each	Removing Inlets (Partial)
210A000	75	CUYD	Unclassified Excavation
210D001	50	CUYD	Borrow Excavation (Loose Truckbed Measurement)
214A000	624	CUYD	Structure Excavation
214B001	199	CUYD	Foundation Backfill, Commercial
260A002	5	CUYD	Cement Mortar Flowable Backfill, Mix 3
305B077	290	Ton	Crushed Aggregate, Section 825, For Miscellaneous Use
405A000	15	Gal	Tack Coat
424A359	5	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 3/8" Maximum Aggregate Size Mix, ESAL Range C/D
424B654	25	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
533A099	637	LF	24" Storm Sewer Pipe (Class 3 R.C.)
533A347	4	LF	15" Storm Sewer Pipe (Class 3 R.C.) (Extension)
534F000	180	LF	Cleaning Existing Culvert (Greater Than 48" Horizontal Opening)
600A000	1	LS	Mobilization
610D003	70	SQYD	Filter Blanket, Geotextile
618A000	175	SQYD	Concrete Sidewalk, 4" Thick
618B003	130	SQYD	Concrete Driveway, 6" Thick (Includes Wire Mesh)
620A000	5	CUYD	Minor Structure Concrete
621C015	4	Each	Inlets, Type S1 Or S3 (1 Wing)
621C017	1	Each	Inlets, Type S1 Or S3 (2 Wing)
621C094	1	Each	Inlets, Type S1 Or S3 (Partial)
623A001	204	LF	Concrete Gutter (Valley)
623C000	465	LF	Combination Curb & Gutter, Type C
650A000	20	CUYD	Topsoil
654A001	130	SQYD	Solid Sodding (Bermuda)
665E000	500	SQYD	Polyethylene
665G000	200	Each	Sand Bags
665J002	50	LF	Silt Fence
665O001	50	LF	Silt Fence Removal
665P005	6	Each	Inlet Protection, Stage 3 Or 4

Item No.	Quantity	Units	Description
665Q002	100	LF	Wattle
674A000	700	LF	Construction Safety Fence
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 22,100.00)
740B000	432	SQFT	Construction Signs
740D000	100	Each	Channelizing Drums
740E000	50	Each	Cones (36 Inches High)
740F001	4	Each	Barricades, Type II
740M001	50	Each	Ballast For Cone
741C010	1	Each	Portable Sequential Arrow And Chevron Sign Unit