

**Alabama Department of Transportation
Proposal Item Summary**

011. NH-0002(604)

LIMESTONE COUNTY

Contract Time: 60 Working Days

DBE Goal Percent: 6.00

for constructing the Micro-Milling, Resurfacing, and Traffic Stripe on SR-2 (US-72) from the intersection of Shaw Road to the junction of York Lane west of Athens. Length 5.989 mi.

The Bracket Estimate on this project is from \$2,703,880 to \$3,304,743.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$3.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206E008	1	Each	Removing Guardrail End Anchor (All Type)
405A000	20,973	Gal	Tack Coat
408B001	209,722	SQYD	Micro-Milling Existing Pavement (Approximately 1.10" Thru 2.00" Thick)
410H000	1	Each	Material Remixing Device
424A360	17,090	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424A369	213	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B655	1,500	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B657	500	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
430B042	932	Ton	Aggregate Surfacing (Crushed Aggregate Base, Type A)
600A000	1	LS	Mobilization
630C080	1	Each	Guardrail End Anchor, Type 20 Series (MASH)
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 158,000.00)
701A227	13	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	13	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	12	Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701A244	12	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	2,670	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	48	Mile	Broken Temporary Traffic Stripe
701C001	51	Mile	Solid Temporary Traffic Stripe
703A002	4,578	SQFT	Traffic Control Markings, Class 2, Type A
703B002	314	SQFT	Traffic Control Legends, Class 2, Type A
703D001	1,412	SQFT	Temporary Traffic Control Markings
705A030	800	Each	Pavement Markers, Class A-H, Type 2-C
705A032	335	Each	Pavement Markers, Class A-H, Type 1-B
705A037	1,600	Each	Pavement Markers, Class A-H, Type 2-D
705A038	170	Each	Pavement Markers, Class A-H, Type 2-E
731B000	1	Each	Pole for Mounting Traffic Detection Equipment
740B000	1,162	SQFT	Construction Signs
740D000	100	Each	Channelizing Drums
740E000	300	Each	Cones (36 Inches High)
740M001	300	Each	Ballast For Cone
741C010	2	Each	Portable Sequential Arrow And Chevron Sign Unit