

**Alabama Department of Transportation
Proposal Item Summary**

013. NH-0020(533)

LAWRENCE COUNTY

Contract Time: 50 Working Days

DBE Goal Percent: 6.00

for constructing the Micro-Milling, Resurfacing, and Traffic Stripe on SR-20 from the Colbert County Line to the junction of CR-585 west of Courtland. Length 5.157 mi.

The Bracket Estimate on this project is from \$2,483,164 to \$3,034,978.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$9.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206E008	1	Each	Removing Guardrail End Anchor (All Type)
405A000	19,730	Gal	Tack Coat
408B001	197,297	SQYD	Micro-Milling Existing Pavement (Approximately 1.10" Thru 2.00" Thick)
410H000	1	Each	Material Remixing Device
424A340	1,763	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424A360	13,807	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424A369	708	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B655	1,500	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B657	500	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
428A001	8	Mile	Scoring Bituminous Pavement Surface
430B042	582	Ton	Aggregate Surfacing (Crushed Aggregate Base, Type A)
600A000	1	LS	Mobilization
630C080	1	Each	Guardrail End Anchor, Type 20 Series (MASH)
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 133,200.00)
701A227	11	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	11	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	11	Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701B207	4,075	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	21	Mile	Broken Temporary Traffic Stripe
701C001	43	Mile	Solid Temporary Traffic Stripe
703A002	3,436	SQFT	Traffic Control Markings, Class 2, Type A
703B002	90	SQFT	Traffic Control Legends, Class 2, Type A
703D001	1,520	SQFT	Temporary Traffic Control Markings
705A030	710	Each	Pavement Markers, Class A-H, Type 2-C
705A032	385	Each	Pavement Markers, Class A-H, Type 1-B
705A037	15	Each	Pavement Markers, Class A-H, Type 2-D
705A038	195	Each	Pavement Markers, Class A-H, Type 2-E
730H001	4,010	LF	Loop Wire
730L005	55	LF	2", Non-Metallic, Conduit
730Q020	4	Each	Miscellaneous Equipment, Backplate for Existing Vehicular Signal Head, 3 Section
730Q022	4	Each	Miscellaneous Equipment, Backplate for Existing Vehicular Signal Head, 5 Section
740B000	1,850	SQFT	Construction Signs
740D000	100	Each	Channelizing Drums
740E000	300	Each	Cones (36 Inches High)
740M001	300	Each	Ballast For Cone

Item No.	Quantity	Units	Description
741C010	2 Each		Portable Sequential Arrow And Chevron Sign Unit