

**Alabama Department of Transportation
Proposal Item Summary**

014. NH-0021(578)

COOSA COUNTY

Contract Time: 30 Working Days

DBE Goal Percent: 3.00

for constructing the Micro-Milling, Resurfacing (Scrub Seal), and Traffic Stripe on SR-21 (US-231) in Rockford from 0.560 mile south of the intersection of SR-22 to the junction of CR-59 north of Rockford. Length 3.316 mi.

The Bracket Estimate on this project is from \$1,533,485 to \$1,874,259.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$9.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
405A000	9,257	Gal	Tack Coat
408B001	84,154	SQYD	Micro-Milling Existing Pavement (Approximately 1.10" Thru 2.00" Thick)
410H000	1	Each	Material Remixing Device
424A360	6,924	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B654	300	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B657	100	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B692	200	Ton	Superpave Bituminous Concrete Lower Binder Layer, Widening, 1" Maximum Aggregate Size Mix, ESAL Range C/D
428A001	3	Mile	Scoring Bituminous Pavement Surface
430B043	200	Ton	Aggregate Surfacing (1" Down, Crusher Run)
433A000	92,569	SQYD	Scrub Seal
600A000	1	LS	Mobilization
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 90,000.00)
701A227	7	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	7	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	6	Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701A270	1	Mile	Solid White, Class 2 Type A Traffic Stripe (10" wide)
701B063	1,250	LF	Dotted, Class 2, Type A Traffic Stripe(Lane Drop 10" Wide)
701C000	16	Mile	Broken Temporary Traffic Stripe
701C001	42	Mile	Solid Temporary Traffic Stripe
701G256	2,000	LF	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
703A002	1,000	SQFT	Traffic Control Markings, Class 2, Type A
703B002	45	SQFT	Traffic Control Legends, Class 2, Type A
703D001	570	SQFT	Temporary Traffic Control Markings
705A030	700	Each	Pavement Markers, Class A-H, Type 2-C
705A032	155	Each	Pavement Markers, Class A-H, Type 1-B
705A037	415	Each	Pavement Markers, Class A-H, Type 2-D
705A038	70	Each	Pavement Markers, Class A-H, Type 2-E
740B000	1,084	SQFT	Construction Signs
740D000	50	Each	Channelizing Drums
740E000	50	Each	Cones (36 Inches High)
740M001	50	Each	Ballast For Cone
740O000	1	Each	Pilot Car