

**Alabama Department of Transportation
Proposal Item Summary**

025. STPAA-0015(542)

PIKE COUNTY

Contract Time: 30 Working Days

DBE Goal Percent: 0.50

for constructing the Planing, Resurfacing, and Traffic Stripe on SR-15 (US-29) from a point north of the SR-53 (US-231) Overpass (MP 102.236) to the junction of Needmore Road in Troy. Length 3.421 mi.

The Bracket Estimate on this project is from \$1,272,145 to \$1,554,844.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$7.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206D001	700	LF	Removing Guardrail
206E008	2	Each	Removing Guardrail End Anchor (All Type)
405A000	10,370	Gal	Tack Coat
408A052	69,142	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
410H000	1	Each	Material Remixing Device
424A360	5,704	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B655	200	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B701	500	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 3/8" Maximum Aggregate Size mix, ESAL Range C/D
430B043	50	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
630A001	663	LF	Steel Beam Guardrail, Class A, Type 2
630A034	38	LF	Steel Beam Guardrail, Class A, Type 2 (8'-0" Post)
630C080	2	Each	Guardrail End Anchor, Type 20 Series (MASH)
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 67,000.00)
701A227	8	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	6	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	1	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	2,838	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	1	Mile	Broken Temporary Traffic Stripe
701C001	28	Mile	Solid Temporary Traffic Stripe
701D007	1	Mile	Solid Traffic Stripe Removed (Paint)
701D008	1	Mile	Solid Traffic Stripe Removed (Plastic)
701D014	1	Mile	Broken Traffic Stripe Removed (Paint)
701D015	1	Mile	Broken Traffic Stripe Removed (Plastic)
703A002	6,390	SQFT	Traffic Control Markings, Class 2, Type A
703B002	1,496	SQFT	Traffic Control Legends, Class 2, Type A
703D001	10,630	SQFT	Temporary Traffic Control Markings
703E001	1,093	SQFT	Temporary Traffic Control Legends
703H000	3	SQFT	Specialty Traffic Control Markings
705A030	1,786	Each	Pavement Markers, Class A-H, Type 2-C
705A032	124	Each	Pavement Markers, Class A-H, Type 1-B
705A037	3,700	Each	Pavement Markers, Class A-H, Type 2-D
705A038	88	Each	Pavement Markers, Class A-H, Type 2-E
730H001	1,950	LF	Loop Wire
740B000	1,204	SQFT	Construction Signs
740C000	27	SQFT	Special Construction Signs
740E000	250	Each	Cones (36 Inches High)

Item No.	Quantity	Units	Description
740M001	250	Each	Ballast For Cone
740O000	1	Each	Pilot Car