

**Alabama Department of Transportation
Proposal Item Summary**

027. STPAA-HSIP-0048(507)

RANDOLPH COUNTY

Contract Time: 70 Working Days

DBE Goal Percent: 2.00

for constructing the Micro-Milling, Resurfacing (Scrub Seal), and Traffic Stripe on SR-48 from 0.280 mile west of the junction of CR-531 (MP 24.961) to the Georgia State Line. Length 9.360 mi.

The Bracket Estimate on this project is from \$4,231,672 to \$5,172,043.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$4.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
209A000	6	Each	Mailbox Reset, Single
405A000	17,812	Gal	Tack Coat
408B001	170,389	SQYD	Micro-Milling Existing Pavement (Approximately 1.10" Thru 2.00" Thick)
410H000	1	Each	Material Remixing Device
424A360	13,793	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424A369	500	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B654	600	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B657	500	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B658	9,858	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
428A001	19	Mile	Scoring Bituminous Pavement Surface
430B043	4,411	Ton	Aggregate Surfacing (1" Down, Crusher Run)
433A000	167,048	SQYD	Scrub Seal
600A000	1	LS	Mobilization
630C080	2	Each	Guardrail End Anchor, Type 20 Series (MASH)
630G003	113	LF	Steel Beam Guardrail for Culvert, Class A, Type 2, Case 3
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 246,000.00)
701A227	21	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	19	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	3	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701C000	7	Mile	Broken Temporary Traffic Stripe
701C001	118	Mile	Solid Temporary Traffic Stripe
703A002	2,738	SQFT	Traffic Control Markings, Class 2, Type A
703D001	822	SQFT	Temporary Traffic Control Markings
705A032	115	Each	Pavement Markers, Class A-H, Type 1-B
705A037	1,115	Each	Pavement Markers, Class A-H, Type 2-D
740B000	1,545	SQFT	Construction Signs
740D000	200	Each	Channelizing Drums
740O000	1	Each	Pilot Car