

**Alabama Department of Transportation
Proposal Item Summary**

028. STPAA-0071(503)

JACKSON COUNTY

Contract Time: 35 Working Days

DBE Goal Percent: 6.00

for constructing the Micro-Milling, Resurfacing (Scrub Seal), and Traffic Stripe on SR-71 from the junction of SR-35 in Section to the junction of CR-378 northeast of Dutton. Length 7.305 mi.

The Bracket Estimate on this project is from \$2,119,283 to \$2,590,234.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$6.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity Units	Description
206D001	100 LF	Removing Guardrail
206E008	4 Each	Removing Guardrail End Anchor (All Type)
405A000	10,782 Gal	Tack Coat
408B001	134,764 SQYD	Micro-Milling Existing Pavement (Approximately 1.10" Thru 2.00" Thick)
410H000	1 Each	Material Remixing Device
424A340	8,773 Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424A349	324 Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B640	500 Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range A/B
428A001	15 Mile	Scoring Bituminous Pavement Surface
430B043	3,819 Ton	Aggregate Surfacing (1" Down, Crusher Run)
433A000	129,964 SQYD	Scrub Seal
600A000	1 LS	Mobilization
630A001	50 LF	Steel Beam Guardrail, Class A, Type 2
630C080	4 Each	Guardrail End Anchor, Type 20 Series (MASH)
665Q002	600 LF	Wattle
698A000	1 LS	Construction Fuel (Maximum Bid Limited to \$ 111,760.00)
701A227	15 Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	9 Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	5 Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	150 LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	15 Mile	Broken Temporary Traffic Stripe
701C001	71 Mile	Solid Temporary Traffic Stripe
701G251	600 LF	Solid White, Class 2, Type A Traffic Stripe (6" Wide) (Rumble Strip)
703A002	641 SQFT	Traffic Control Markings, Class 2, Type A
703B002	23 SQFT	Traffic Control Legends, Class 2, Type A
703D001	1,800 SQFT	Temporary Traffic Control Markings
705A030	10 Each	Pavement Markers, Class A-H, Type 2-C
705A032	244 Each	Pavement Markers, Class A-H, Type 1-B
705A037	390 Each	Pavement Markers, Class A-H, Type 2-D
731A021	1 Each	Traffic Counting Units, Type R
731B000	1 Each	Pole for Mounting Traffic Detection Equipment
740B000	1,872 SQFT	Construction Signs
740D000	200 Each	Channelizing Drums
740E000	200 Each	Cones (36 Inches High)
740M001	200 Each	Ballast For Cone
740O000	1 Each	Pilot Car
741C010	2 Each	Portable Sequential Arrow And Chevron Sign Unit