

**Alabama Department of Transportation
Proposal Item Summary**

032. STPAA-FMGR-0010(564)

BARBOUR AND HENRY COUNTIES

Contract Time: 75 Working Days

DBE Goal Percent: 5.00

for constructing the Micro-Milling, Resurfacing, and Traffic Stripe on SR-10 from the junction of CR-41 (Blue Springs Town Limits) to 0.630 mile northwest of the junction of CR-25. Length 10.869 mi.

The Bracket Estimate on this project is from \$3,284,687 to \$4,014,618.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$7.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206D001	3,488	LF	Removing Guardrail
206E008	50	Each	Removing Guardrail End Anchor (All Type)
212A000	566	STA	Machine Grading Shoulders
405A000	17,856	Gal	Tack Coat
408B001	178,558	SQYD	Micro-Milling Existing Pavement (Approximately 1.10" Thru 2.00" Thick)
410H000	1	Each	Material Remixing Device
424A361	18,540	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424A370	75	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B655	500	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B701	100	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 3/8" Maximum Aggregate Size mix, ESAL Range C/D
428A001	22	Mile	Scoring Bituminous Pavement Surface
430B043	200	Ton	Aggregate Surfacing (1" Down, Crusher Run)
502A000	307	LB	Steel Reinforcement
524B011	6	CUYD	Culvert Concrete Extension (Cast In Place)
600A000	1	LS	Mobilization
630A001	2,939	LF	Steel Beam Guardrail, Class A, Type 2
630C079	12	Each	Guardrail End Anchor, Type 13 (MASH)
630C080	38	Each	Guardrail End Anchor, Type 20 Series (MASH)
630G003	86	LF	Steel Beam Guardrail for Culvert, Class A, Type 2, Case 3
650A000	2,835	CUYD	Topsoil
652A100	16	Acre	Seeding
652C000	67	Acre	Mowing
656A010	16	Acre	Mulching
659C002	900	SQYD	Erosion Control Product, Type S2
665A000	48	Acre	Temporary Seeding
665B001	96	Ton	Temporary Mulching
665J002	250	LF	Silt Fence
665O001	250	LF	Silt Fence Removal
665Q002	500	LF	Wattle
666A001	6	Acre	Pest Control Treatment
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 177,400.00)
701A227	22	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	9	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	10	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701C000	20	Mile	Broken Temporary Traffic Stripe
701C001	62	Mile	Solid Temporary Traffic Stripe

Item No.	Quantity	Units	Description
701D007	1	Mile	Solid Traffic Stripe Removed (Paint)
701D008	1	Mile	Solid Traffic Stripe Removed (Plastic)
701D014	1	Mile	Broken Traffic Stripe Removed (Paint)
701D015	1	Mile	Broken Traffic Stripe Removed (Plastic)
701G146	1,968	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G150	984	LF	Broken Yellow, Class W, Type A Traffic Stripe (5" Wide)
701G161	984	LF	Broken Black, Class W, Type B Traffic Stripe (5" Wide)
703A002	1,051	SQFT	Traffic Control Markings, Class 2, Type A
703D001	2,102	SQFT	Temporary Traffic Control Markings
705A030	132	Each	Pavement Markers, Class A-H, Type 2-C
705A032	324	Each	Pavement Markers, Class A-H, Type 1-B
705A037	486	Each	Pavement Markers, Class A-H, Type 2-D
740B000	1,484	SQFT	Construction Signs
740C000	5	SQFT	Special Construction Signs
740E000	150	Each	Cones (36 Inches High)
740M001	150	Each	Ballast For Cone
740O000	1	Each	Pilot Car