

**Alabama Department of Transportation  
Proposal Item Summary**

**037. STPAA-HSIP-0034(503)**

**TALLADEGA COUNTY**

Contract Time: 65 Working Days

DBE Goal Percent: 2.00

for constructing the Micro-Milling, Resurfacing (Scrub Seal), Bridge Guardrail Retrofit, Guardrail Installation, and Traffic Stripe on SR-34 from the St. Clair County Line to the junction of SR-77 north of Talladega. Length 8.241 mi.

The Bracket Estimate on this project is from \$3,229,685 to \$3,947,392.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$4.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
206D001	536	LF	Removing Guardrail
206E008	14	Each	Removing Guardrail End Anchor (All Type)
405A000	12,856	Gal	Tack Coat
408B001	128,551	SQYD	Micro-Milling Existing Pavement (Approximately 1.10" Thru 2.00" Thick)
410H000	1	Each	Material Remixing Device
424A340	11,536	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424A349	250	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B639	250	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
424B642	250	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B643	9,384	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
428A001	17	Mile	Scoring Bituminous Pavement Surface
430B043	1,200	Ton	Aggregate Surfacing (1" Down, Crusher Run)
433A000	128,551	SQYD	Scrub Seal
600A000	1	LS	Mobilization
610D003	500	SQYD	Filter Blanket, Geotextile
629D003	2	Each	Bridge Guardrail Retrofit, Type SC
630A001	325	LF	Steel Beam Guardrail, Class A, Type 2
630C079	2	Each	Guardrail End Anchor, Type 13 (MASH)
630C080	12	Each	Guardrail End Anchor, Type 20 Series (MASH)
665A000	2	Acre	Temporary Seeding
665B001	6	Ton	Temporary Mulching
665G000	100	Each	Sand Bags
665Q002	500	LF	Wattle
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 133,000.00)
701A227	17	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	13	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	3	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B205	518	LF	Dotted, Class 2, Type A, Traffic Stripe
701C000	9	Mile	Broken Temporary Traffic Stripe
701C001	106	Mile	Solid Temporary Traffic Stripe
703A002	649	SQFT	Traffic Control Markings, Class 2, Type A
703B002	45	SQFT	Traffic Control Legends, Class 2, Type A
703D001	616	SQFT	Temporary Traffic Control Markings
705A030	13	Each	Pavement Markers, Class A-H, Type 2-C

<b>Item No.</b>	<b>Quantity</b>	<b>Units</b>	<b>Description</b>
705A032	305	Each	Pavement Markers, Class A-H, Type 1-B
705A037	1,088	Each	Pavement Markers, Class A-H, Type 2-D
705A038	87	Each	Pavement Markers, Class A-H, Type 2-E
740B000	1,270	SQFT	Construction Signs
740D000	50	Each	Channelizing Drums
740E000	50	Each	Cones (36 Inches High)
740M001	50	Each	Ballast For Cone
740O000	1	Each	Pilot Car