

**Alabama Department of Transportation  
Proposal Item Summary**

**038. STPAA-HSIP-0052(521)**

**GENEVA COUNTY**

Contract Time: 70 Working Days

DBE Goal Percent: 2.00

for constructing the Safety Widening, Micro-Milling, Resurfacing, and Traffic Stripe on SR-52 from the intersection of Line Street in Samson to the junction of SR-196 in Geneva. Length 10.060 mi.

The Bracket Estimate on this project is from \$3,451,649 to \$4,218,682.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$7.00 per set.

*The Principal Items of work are approximately as follows:*

| Item No. | Quantity | Units | Description  |
|----------|----------|-------|--|
| 206D001  | 263      | LF    | Removing Guardrail   |
| 206E008  | 2        | Each  | Removing Guardrail End Anchor (All Type)   |
| 209A000  | 10       | Each  | Mailbox Reset, Single  |
| 210D021  | 200      | CUYD  | Borrow Excavation (Loose Truckbed Measurement)(A4 or Better)   |
| 212A000  | 947      | STA   | Machine Grading Shoulders  |
| 405A000  | 17,328   | Gal   | Tack Coat  |
| 408B001  | 161,475  | SQYD  | Micro-Milling Existing Pavement (Approximately 1.10" Thru 2.00" Thick)   |
| 410H000  | 1        | Each  | Material Remixing Device   |
| 424A361  | 13,042   | Ton   | Superpave Bituminous Concrete Wearing Surface Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D           |
| 424A370  | 1,409    | Ton   | Superpave Bituminous Concrete Wearing Surface Layer, Widening, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D |
| 424B655  | 100      | Ton   | Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D      |
| 424B663  | 4,132    | Ton   | Superpave Bituminous Concrete Upper Binder Layer, Widening, 1 1/2" Maximum Aggregate Size Mix, ESAL Range C/D  |
| 424B701  | 100      | Ton   | Superpave Bituminous Concrete Upper Binder Layer, Leveling, 3/8" Maximum Aggregate Size mix, ESAL Range C/D    |
| 428A001  | 9        | Mile  | Scoring Bituminous Pavement Surface  |
| 430B043  | 100      | Ton   | Aggregate Surfacing (1" Down, Crusher Run)   |
| 600A000  | 1        | LS    | Mobilization   |
| 630A001  | 238      | LF    | Steel Beam Guardrail, Class A, Type 2  |
| 630C080  | 2        | Each  | Guardrail End Anchor, Type 20 Series (MASH)  |
| 650A000  | 1,750    | CUYD  | Topsoil  |
| 652A100  | 65       | Acre  | Seeding  |
| 652C000  | 65       | Acre  | Mowing   |
| 656A010  | 65       | Acre  | Mulching   |
| 659C002  | 1,050    | SQYD  | Erosion Control Product, Type S2   |
| 665A000  | 65       | Acre  | Temporary Seeding  |
| 665B001  | 500      | Ton   | Temporary Mulching   |
| 665J002  | 2,500    | LF    | Silt Fence   |
| 665O001  | 2,500    | LF    | Silt Fence Removal   |
| 665P005  | 25       | Each  | Inlet Protection, Stage 3 Or 4   |
| 665Q002  | 2,500    | LF    | Wattle   |
| 666A001  | 65       | Acre  | Pest Control Treatment   |
| 698A000  | 1        | LS    | Construction Fuel (Maximum Bid Limited to \$ 184,000.00)   |
| 701A227  | 20       | Mile  | Solid White, Class 2, Type A Traffic Stripe (5" Wide)  |
| 701A230  | 8        | Mile  | Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)   |
| 701A244  | 13       | Mile  | Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)  |
| 701B207  | 1,606    | LF    | Dotted, Class 2, Type A Traffic Stripe (5" Wide)   |

| Item No. | Quantity | Units | Description                                     |
|----------|----------|-------|---|
| 701C000  | 26       | Mile  | Broken Temporary Traffic Stripe                 |
| 701C001  | 56       | Mile  | Solid Temporary Traffic Stripe                  |
| 701D007  | 1        | Mile  | Solid Traffic Stripe Removed (Paint)            |
| 701D008  | 1        | Mile  | Solid Traffic Stripe Removed (Plastic)          |
| 701D014  | 1        | Mile  | Broken Traffic Stripe Removed (Paint)           |
| 701D015  | 1        | Mile  | Broken Traffic Stripe Removed (Plastic)         |
| 703A002  | 25,602   | SQFT  | Traffic Control Markings, Class 2, Type A       |
| 703B002  | 516      | SQFT  | Traffic Control Legends, Class 2, Type A        |
| 703D001  | 3,616    | SQFT  | Temporary Traffic Control Markings              |
| 705A030  | 237      | Each  | Pavement Markers, Class A-H, Type 2-C           |
| 705A032  | 348      | Each  | Pavement Markers, Class A-H, Type 1-B           |
| 705A037  | 487      | Each  | Pavement Markers, Class A-H, Type 2-D           |
| 705A038  | 535      | Each  | Pavement Markers, Class A-H, Type 2-E           |
| 707H001  | 75       | LF    | Raised Curb Channelizer, White                  |
| 740B000  | 2,066    | SQFT  | Construction Signs                              |
| 740E000  | 250      | Each  | Cones (36 Inches High)                          |
| 740M001  | 250      | Each  | Ballast For Cone                                |
| 740O000  | 1        | Each  | Pilot Car                                       |
| 741C010  | 1        | Each  | Portable Sequential Arrow And Chevron Sign Unit |