

**Alabama Department of Transportation
Proposal Item Summary**

042. STPSU-0819(255)

CALHOUN COUNTY

Contract Time: 35 Working Days

DBE Goal Percent: 3.00

for constructing the Micro-Milling, Resurfacing, and Traffic Stripe on George Douthit Drive Southwest from the junction of Brierwood Place Southwest to the intersection of SR-21 in Jacksonville. Length 1.108 mi.

The Bracket Estimate on this project is from \$494,133 to \$603,941.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$11.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206C000	24	SQYD	Removing Concrete Sidewalk
206D003	56	LF	Removing Curb And Gutter
405A000	2,066	Gal	Tack Coat
408B001	20,660	SQYD	Micro-Milling Existing Pavement (Approximately 1.10" Thru 2.00" Thick)
424A360	2,015	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B654	50	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
600A000	1	LS	Mobilization
614A000	18	CUYD	Slope Paving
618A000	25	SQYD	Concrete Sidewalk, 4" Thick
618C001	112	SQFT	Detectable Warning Surface
618D000	78	SQYD	Curb Ramp
623C000	15	LF	Combination Curb & Gutter, Type C
665G000	250	Each	Sand Bags
665J002	212	LF	Silt Fence
665O001	212	LF	Silt Fence Removal
665Q002	120	LF	Wattle
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 26,180.00)
701A231	2	Mile	Solid White, Class 2, Type A Traffic Stripe
701A235	3	Mile	Solid Yellow, Class 2, Type A Traffic Stripe
701B205	702	LF	Dotted, Class 2, Type A, Traffic Stripe
701C003	12	Mile	Solid Temporary Traffic Stripe (Paint)
701D007	12	Mile	Solid Traffic Stripe Removed (Paint)
701F001	1,404	LF	Dotted Temporary Traffic Stripe (Paint)
701H010	1,404	LF	Dotted Traffic Stripe Removed (Paint)
703A002	2,769	SQFT	Traffic Control Markings, Class 2, Type A
703B002	135	SQFT	Traffic Control Legends, Class 2, Type A
703D001	2,769	SQFT	Temporary Traffic Control Markings
703H000	72	SQFT	Specialty Traffic Control Markings
705A030	59	Each	Pavement Markers, Class A-H, Type 2-C
705A032	112	Each	Pavement Markers, Class A-H, Type 1-B
705A037	144	Each	Pavement Markers, Class A-H, Type 2-D
705A038	47	Each	Pavement Markers, Class A-H, Type 2-E
710A150	51	SQFT	Class 9, Aluminum Flat Sign Panels 0.08" Thick (Type XI Background)
710A155	93	SQFT	Class 9, Aluminum Flat Sign Panels 0.08" Thick (Type XI Background, Fluorescent)
710B021	144	LF	Roadway Sign Post (#3 U Channel, Galvanized Steel or 2", 14 Ga Square Tubular Steel)
740B000	516	SQFT	Construction Signs
740D000	250	Each	Channelizing Drums

Item No.	Quantity	Units	Description
740E000	100	Each	Cones (36 Inches High)
740M001	100	Each	Ballast For Cone