

**Alabama Department of Transportation
Proposal Item Summary**

005. IM-I459(322)

JEFFERSON COUNTY

Contract Time: 130 Working Days

DBE Goal Percent: 1.00

for constructing the Traffic Sign Replacements on I-459 from the I-20/I-59 Interchange (Exit 0) in McCalla to the I-59 Interchange (Exit 33).

The Bracket Estimate on this project is from \$2,438,201 to \$2,980,023.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$41.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
600A000	1	LS	Mobilization
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 139,000.00)
710A187	35,197	SQFT	Class 6 Aluminum Multiple Flat Sign Panels 0.125" Thick (Type IV or XI Background)
710B008	1,400	LF	Roadway Sign Post (W8 x 18 Steel Beam)
710B011	650	LF	Roadway Sign Post (W6 x 12 Steel Beam)
710B023	4,032	LF	Roadway Sign Post (2 1/2", 12 Ga Square Tubular Steel With Breakaway Slip Base System)
710B050	4,032	LF	Roadway Sign Post (2 1/4", 12 Ga Square Tubular Steel)(Stiffener)
710E000	1,000	LF	Overhead Roadway Sign Hangers, W6 X 9
728A000	2	Each	Truck Mounted Impact Attenuator Unit
740B000	2,056	SQFT	Construction Signs
740C000	174	SQFT	Special Construction Signs
740D000	500	Each	Channelizing Drums
741C010	4	Each	Portable Sequential Arrow And Chevron Sign Unit
742A001	2	Each	Portable Changeable Message Sign, Type 2
745A000	600	HOUR	Uniformed Police Officer