

**Alabama Department of Transportation
Proposal Item Summary**

**011. NH-HSIP-0003(657)
ESCAMBIA COUNTY**

Contract Time: December 31, 2024 Completion Date

DBE Goal Percent: 1.00

for constructing the Micro-Milling, Resurfacing (Micro-Surfacing Seal Coat, Type II and Type III), Traffic Signal Upgrades, and Traffic Stripe on SR-3 (US-31) from the junction of Old Highway 31 (MP 64.774) to a point south of the Burnt Corn Creek Bridge (MP 69.076) in Brewton. Length 4.301 mi.

The Bracket Estimate on this project is from \$2,060,095 to \$2,517,894.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$9.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206D001	663	LF	Removing Guardrail
206E008	8	Each	Removing Guardrail End Anchor (All Type)
403B000	1,001	Ton	Micro-Surfacing Seal Coat, Type II
403B001	1,025	Ton	Micro-Surfacing Seal Coat, Type III
405A000	5,120	Gal	Tack Coat
408B000	93,129	SQYD	Micro-Milling Existing Pavement (Approximately 0.00" Thru 1.00" Thick)
408B001	65,129	SQYD	Micro-Milling Existing Pavement (Approximately 1.10" Thru 2.00" Thick)
424A360	4,224	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424A369	1,150	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B653	200	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B657	200	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
428A001	12	Mile	Scoring Bituminous Pavement Surface
600A000	1	LS	Mobilization
630A001	663	LF	Steel Beam Guardrail, Class A, Type 2
630C077	1	Each	Guardrail End Anchor, Type 8 (MASH)
630C079	1	Each	Guardrail End Anchor, Type 13 (MASH)
630C080	6	Each	Guardrail End Anchor, Type 20 Series (MASH)
650A000	500	CUYD	Topsoil
652A100	5	Acre	Seeding
652C000	12	Acre	Mowing
654A001	444	SQYD	Solid Sodding (Bermuda)
656A010	5	Acre	Mulching
665J002	1,000	LF	Silt Fence
665O001	1,000	LF	Silt Fence Removal
665Q002	500	LF	Wattle
666A001	1	Acre	Pest Control Treatment
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 110,000.00)
701A227	10	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	9	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	9	Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701B207	7,960	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	29	Mile	Broken Temporary Traffic Stripe
701C001	54	Mile	Solid Temporary Traffic Stripe
701G142	1,082	LF	Broken White, Class W, Type A Traffic Stripe (5" Wide)
701G146	1,082	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)

Item No.	Quantity	Units	Description
701G154	1,082	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
701G161	1,082	LF	Broken Black, Class W, Type B Traffic Stripe (5" Wide)
701G256	1,195	LF	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701H001	2,164	LF	Solid Traffic Stripe Removed (Plastic)
701H006	1,082	LF	Broken Traffic Stripe Removed (Plastic)
703A002	2,850	SQFT	Traffic Control Markings, Class 2, Type A
703B002	449	SQFT	Traffic Control Legends, Class 2, Type A
703D001	2,053	SQFT	Temporary Traffic Control Markings
703E001	449	SQFT	Temporary Traffic Control Legends
705A030	720	Each	Pavement Markers, Class A-H, Type 2-C
705A032	169	Each	Pavement Markers, Class A-H, Type 1-B
705A037	171	Each	Pavement Markers, Class A-H, Type 2-D
705A038	84	Each	Pavement Markers, Class A-H, Type 2-E
730H001	2,636	LF	Loop Wire
730I001	1,805	LF	Loop Detector Lead-In-Cable
730K001	5	Each	Traffic Signal Junction Box Type S1
730L005	341	LF	2", Non-Metallic, Conduit
730Q020	6	Each	Miscellaneous Equipment, Backplate for Existing Vehicular Signal Head, 3 Section
730Q022	2	Each	Miscellaneous Equipment, Backplate for Existing Vehicular Signal Head, 5 Section
740B000	1,596	SQFT	Construction Signs
740D000	25	Each	Channelizing Drums
740E000	200	Each	Cones (36 Inches High)
740M001	200	Each	Ballast For Cone
741C010	2	Each	Portable Sequential Arrow And Chevron Sign Unit