

**Alabama Department of Transportation  
Proposal Item Summary**

**012. NH-HSIP-0074(548)**

**ETOWAH COUNTY**

Contract Time: 40 Working Days

DBE Goal Percent: 4.00

for constructing the Safety Widening, Micro-Milling, Resurfacing (Scrub Seal), and Traffic Stripe on SR-74 (US-278) from the intersection of Alford Ben Road in Hokes Bluff to the Calhoun County Line. Length 7.370 mi.

The Bracket Estimate on this project is from \$2,089,258 to \$2,553,538.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$5.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
405A000	14,810	Gal	Tack Coat
408B000	117,801	SQYD	Micro-Milling Existing Pavement (Approximately 0.00" Thru 1.00" Thick)
410H000	1	Each	Material Remixing Device
424A356	5,964	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/8" Maximum Aggregate Size Mix, ESAL Range C/D
424A359	190	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 3/8" Maximum Aggregate Size Mix, ESAL Range C/D
424B655	1,000	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B662	3,068	Ton	Superpave Bituminous Concrete Upper Binder Layer, Widening, 1" Maximum Aggregate Size Mix, ESAL Range C/D
428A001	15	Mile	Scoring Bituminous Pavement Surface
430B043	3,905	Ton	Aggregate Surfacing (1" Down, Crusher Run)
433A000	105,178	SQYD	Scrub Seal
600A000	1	LS	Mobilization
610D003	500	SQYD	Filter Blanket, Geotextile
665J002	200	LF	Silt Fence
665O001	200	LF	Silt Fence Removal
665Q002	200	LF	Wattle
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 112,000.00)
701A227	15	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	9	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	5	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701C000	15	Mile	Broken Temporary Traffic Stripe
701C001	71	Mile	Solid Temporary Traffic Stripe
703A002	432	SQFT	Traffic Control Markings, Class 2, Type A
703D001	1,296	SQFT	Temporary Traffic Control Markings
705A031	100	Each	Pavement Markers, Class A-H, Type 1-A
705A032	260	Each	Pavement Markers, Class A-H, Type 1-B
705A037	679	Each	Pavement Markers, Class A-H, Type 2-D
740B000	1,406	SQFT	Construction Signs
740D000	200	Each	Channelizing Drums
740E000	200	Each	Cones (36 Inches High)
740M001	200	Each	Ballast For Cone
740O000	1	Each	Pilot Car
741C010	2	Each	Portable Sequential Arrow And Chevron Sign Unit