

**Alabama Department of Transportation
Proposal Item Summary**

018. STPAA-0083(503)

MONROE AND CONECHU COUNTIES

Contract Time: December 31, 2024 Completion Date

DBE Goal Percent: 1.50

for constructing the Resurfacing (Scrub Seal) and Traffic Stripe on SR-83 from the Conecuh County Line to the junction of SR-47 southeast of Beatrice. Length 2.603 mi.

The Bracket Estimate on this project is from \$724,174 to \$885,102.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$5.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
212A000	275	STA	Machine Grading Shoulders
405A000	2,189	Gal	Tack Coat
410H000	1	Each	Material Remixing Device
424A336	2,500	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/8" Maximum Aggregate Size Mix, ESAL Range A/B
424A339	30	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 3/8" Maximum Aggregate Size Mix, ESAL Range A/B
424B640	200	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range A/B
424B700	300	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 3/8" Maximum Aggregate Size mix, ESAL Range A/B
430B043	100	Ton	Aggregate Surfacing (1" Down, Crusher Run)
433A000	39,705	SQYD	Scrub Seal
600A000	1	LS	Mobilization
650A000	700	CUYD	Topsoil
652A100	4	Acre	Seeding
652C000	50	Acre	Mowing
656A010	4	Acre	Mulching
665Q002	150	LF	Wattle
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 38,000.00)
701A227	6	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	4	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	2	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701C000	3	Mile	Broken Temporary Traffic Stripe
701C001	18	Mile	Solid Temporary Traffic Stripe
701D005	9	Mile	Solid Traffic Stripe Removed
701D013	2	Mile	Broken Traffic Stripe Removed
701G252	300	LF	Solid White, Class 2, Type A Traffic Stripe (5" Wide) (Rumble Strip)
703B002	56	SQFT	Traffic Control Legends, Class 2, Type A
705A032	79	Each	Pavement Markers, Class A-H, Type 1-B
705A037	173	Each	Pavement Markers, Class A-H, Type 2-D
740B000	608	SQFT	Construction Signs
740E000	50	Each	Cones (36 Inches High)
740M001	50	Each	Ballast For Cone
740O000	1	Each	Pilot Car