

**Alabama Department of Transportation
Proposal Item Summary**

022. STPAA-FMGR-0076(507)

SHELBY COUNTY

Contract Time: 30 Working Days

DBE Goal Percent: 2.00

for constructing the Resurfacing (Micro-Surfacing Seal Coat, Type II and Type III), Guardrail Installation, and Traffic Stripe on SR-76 from the junction of SR-25 in Harpersville to the junction of SR-38 (US-280). Length 4.859 mi.

The Bracket Estimate on this project is from \$747,962 to \$914,176.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$6.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206D001	50	LF	Removing Guardrail
206E008	4	Each	Removing Guardrail End Anchor (All Type)
403B000	630	Ton	Micro-Surfacing Seal Coat, Type II
403B001	1,050	Ton	Micro-Surfacing Seal Coat, Type III
424B653	500	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
428A001	15	Mile	Scoring Bituminous Pavement Surface
600A000	1	LS	Mobilization
630C080	4	Each	Guardrail End Anchor, Type 20 Series (MASH)
631C010	100	LF	Guardrail Reset
631E003	4	Each	Guardrail End Anchor, Type 13, Reset
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 52,500.00)
701A227	11	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	5	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	4	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701C000	8	Mile	Broken Temporary Traffic Stripe
701C001	29	Mile	Solid Temporary Traffic Stripe
705A032	122	Each	Pavement Markers, Class A-H, Type 1-B
705A037	288	Each	Pavement Markers, Class A-H, Type 2-D
740B000	638	SQFT	Construction Signs
740C000	36	SQFT	Special Construction Signs
740E000	100	Each	Cones (36 Inches High)
740M001	100	Each	Ballast For Cone
740O000	1	Each	Pilot Car