

**Alabama Department of Transportation
Proposal Item Summary**

026. STPAA-HSIP-0027(520)

COFFEE COUNTY

Contract Time: 45 Working Days

DBE Goal Percent: 0.50

for constructing the Safety Widening, Resurfacing, and Traffic Stripe on SR-27 from the Coffee County Line to a point near MP 22.774 (4-Lane Section) southwest of Enterprise. Length 4.595 mi.

The Bracket Estimate on this project is from \$1,569,724 to \$1,918,551.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$6.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
209A000	6	Each	Mailbox Reset, Single
210D021	100	CUYD	Borrow Excavation (Loose Truckbed Measurement)(A4 or Better)
212A000	480	STA	Machine Grading Shoulders
401B100	66,602	SQYD	Bituminous Treatment E (With Polymer Additive)
405A000	8,047	Gal	Tack Coat
410H000	1	Each	Material Remixing Device
424A341	6,689	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
424A350	370	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
424B640	100	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range A/B
424B648	1,900	Ton	Superpave Bituminous Concrete Upper Binder Layer, Widening, 1 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B700	100	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 3/8" Maximum Aggregate Size mix, ESAL Range A/B
428A001	10	Mile	Scoring Bituminous Pavement Surface
430B043	100	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
650A000	1,151	CUYD	Topsoil
652A100	5	Acre	Seeding
652C000	29	Acre	Mowing
656A010	5	Acre	Mulching
659C002	356	SQYD	Erosion Control Product, Type S2
665A000	14	Acre	Temporary Seeding
665B001	27	Ton	Temporary Mulching
665E000	500	SQYD	Polyethylene
665G000	100	Each	Sand Bags
665J002	500	LF	Silt Fence
665O001	500	LF	Silt Fence Removal
665P005	2	Each	Inlet Protection, Stage 3 Or 4
665Q002	820	LF	Wattle
666A001	5	Acre	Pest Control Treatment
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 83,000.00)
701A227	9	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	7	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	3	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701C000	5	Mile	Broken Temporary Traffic Stripe
701C001	31	Mile	Solid Temporary Traffic Stripe
701D007	1	Mile	Solid Traffic Stripe Removed (Paint)

Item No.	Quantity	Units	Description
701D008	1	Mile	Solid Traffic Stripe Removed (Plastic)
701D014	1	Mile	Broken Traffic Stripe Removed (Paint)
701D015	1	Mile	Broken Traffic Stripe Removed (Plastic)
703A002	551	SQFT	Traffic Control Markings, Class 2, Type A
703D001	741	SQFT	Temporary Traffic Control Markings
705A030	32	Each	Pavement Markers, Class A-H, Type 2-C
705A032	115	Each	Pavement Markers, Class A-H, Type 1-B
705A037	314	Each	Pavement Markers, Class A-H, Type 2-D
740B000	1,036	SQFT	Construction Signs
740E000	150	Each	Cones (36 Inches High)
740M001	150	Each	Ballast For Cone
740O000	1	Each	Pilot Car