

**Alabama Department of Transportation
Proposal Item Summary**

028. STPAA-HSIP-0605(501)

HOUSTON AND DALE COUNTIES

Contract Time: 75 Working Days

DBE Goal Percent: 3.00

for constructing the Safety Widening, Micro-Milling, Resurfacing, Bridge Guardrail Retrofit, and Traffic Stripe on SR-605 from the intersection of Fortner Street in Dothan to the junction of SR-53 (US-231). Length 6.851 mi.

The Bracket Estimate on this project is from \$3,105,087 to \$3,795,106.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$11.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206C010	649	SQYD	Removing Concrete Driveway
206D001	250	LF	Removing Guardrail
206D002	15	LF	Removing Curb
206D003	13	LF	Removing Curb And Gutter
206E008	16	Each	Removing Guardrail End Anchor (All Type)
209A000	8	Each	Mailbox Reset, Single
210A000	48	CUYD	Unclassified Excavation
210D021	34	CUYD	Borrow Excavation (Loose Truckbed Measurement)(A4 or Better)
212A000	641	STA	Machine Grading Shoulders
405A000	13,065	Gal	Tack Coat
408B001	116,399	SQYD	Micro-Milling Existing Pavement (Approximately 1.10" Thru 2.00" Thick)
410H000	1	Each	Material Remixing Device
424A361	14,175	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424A370	269	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B655	100	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B663	2,536	Ton	Superpave Bituminous Concrete Upper Binder Layer, Widening, 1 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B701	100	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 3/8" Maximum Aggregate Size mix, ESAL Range C/D
428A001	13	Mile	Scoring Bituminous Pavement Surface
430B043	75	Ton	Aggregate Surfacing (1" Down, Crusher Run)
502A000	225	LB	Steel Reinforcement
524B011	3	CUYD	Culvert Concrete Extension (Cast In Place)
600A000	1	LS	Mobilization
610C001	27	Ton	Loose Riprap, Class 2
610D003	33	SQYD	Filter Blanket, Geotextile
623B001	15	LF	Concrete Curb, Type N Special
623C000	10	LF	Combination Curb & Gutter, Type C
629D005	4	Each	Bridge Guardrail Retrofit, Type 13 (MASH)
630A001	475	LF	Steel Beam Guardrail, Class A, Type 2
630C079	4	Each	Guardrail End Anchor, Type 13 (MASH)
630C080	12	Each	Guardrail End Anchor, Type 20 Series (MASH)
630G003	75	LF	Steel Beam Guardrail for Culvert, Class A, Type 2, Case 3
650A000	2,623	CUYD	Topsoil
652A100	9	Acre	Seeding
652C000	51	Acre	Mowing
654A001	45	SQYD	Solid Sodding (Bermuda)

Item No.	Quantity	Units	Description
656A010	9	Acre	Mulching
659C002	1,000	SQYD	Erosion Control Product, Type S2
665A000	9	Acre	Temporary Seeding
665B001	27	Ton	Temporary Mulching
665E000	400	SQYD	Polyethylene
665G000	200	Each	Sand Bags
665J002	800	LF	Silt Fence
665O001	800	LF	Silt Fence Removal
665P005	34	Each	Inlet Protection, Stage 3 Or 4
665Q002	1,000	LF	Wattle
666A001	9	Acre	Pest Control Treatment
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 162,610.00)
701A227	20	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	11	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	4	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	3,677	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	8	Mile	Broken Temporary Traffic Stripe
701C001	61	Mile	Solid Temporary Traffic Stripe
701D007	1	Mile	Solid Traffic Stripe Removed (Paint)
701D008	1	Mile	Solid Traffic Stripe Removed (Plastic)
701D014	1	Mile	Broken Traffic Stripe Removed (Paint)
701D015	1	Mile	Broken Traffic Stripe Removed (Plastic)
701G146	748	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G154	748	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
703A002	8,989	SQFT	Traffic Control Markings, Class 2, Type A
703B002	830	SQFT	Traffic Control Legends, Class 2, Type A
703D001	4,524	SQFT	Temporary Traffic Control Markings
705A002	72	Each	Pavement Markers, Class A, Type 2-A
705A030	484	Each	Pavement Markers, Class A-H, Type 2-C
705A032	1,402	Each	Pavement Markers, Class A-H, Type 1-B
705A037	659	Each	Pavement Markers, Class A-H, Type 2-D
705A038	884	Each	Pavement Markers, Class A-H, Type 2-E
726A000	140	LF	Portable Concrete Safety Barriers, Type 6
726D026	2	Each	Portable Impact Attenuator Assembly (Bi-directional,TL-3)
730H001	6,800	LF	Loop Wire
740B000	2,497	SQFT	Construction Signs
740C000	41	SQFT	Special Construction Signs
740D000	50	Each	Channelizing Drums
740E000	250	Each	Cones (36 Inches High)
740M001	250	Each	Ballast For Cone
740O000	1	Each	Pilot Car