

**Alabama Department of Transportation
Proposal Item Summary**

008. DEMO-A209(250)

WASHINGTON COUNTY

Contract Time: 30 Working Days

for constructing the Resurfacing and Traffic Stripe on CR-11 (Copeland Road); on 2nd Avenue; on 3rd Avenue; on 4th Avenue; on Main Street; and on Long Street in Millry. Length 1.149 mi.

The Bracket Estimate on this project is from \$197,030 to \$240,814.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$4.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
405A000	1,314	Gal	Tack Coat
424A341	1,084	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
424B640	50	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range A/B
424B643	50	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
430B043	50	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
622A000	1	Each	Manhole Covers Reset
650A000	150	CUYD	Topsoil
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 10,000.00)
701A034	1	Mile	Solid Yellow, Class 2T, Type A Traffic Stripe
703A004	300	SQFT	Traffic Control Markings, Class 2T, Type A
703D001	300	SQFT	Temporary Traffic Control Markings
740B000	410	SQFT	Construction Signs
740E000	150	Each	Cones (36 Inches High)
740M001	150	Each	Ballast For Cone