

**Alabama Department of Transportation  
Proposal Item Summary**

---

**011. HRRR-6023(251)**

**SUMTER COUNTY**

Contract Time: 35 Working Days

for constructing the Roadway Safety Improvements (Pavement Markers, Traffic Signs, and Traffic Stripe) at various locations on CR-21 from the junction of SR-28 southeast of Livingston to a point 600 feet south of the junction of the Port of Epes Highway southeast of Epes. Length 8.820 mi.

The Bracket Estimate on this project is from \$191,871 to \$234,509.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$4.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
600A000	1	LS	Mobilization
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 6,000.00)
701A231	18	Mile	Solid White, Class 2, Type A Traffic Stripe
701A235	18	Mile	Solid Yellow, Class 2, Type A Traffic Stripe
701A245	2	Mile	Broken Yellow, Class 2, Type A Traffic Stripe
703A002	100	SQFT	Traffic Control Markings, Class 2, Type A
705A032	190	Each	Pavement Markers, Class A-H, Type 1-B
705A037	977	Each	Pavement Markers, Class A-H, Type 2-D
707B014	4	Each	Type B Object Marker Installation
710A160	40	SQFT	Class 10 Aluminum Flat Sign Panels 0.08" Thick (Type XI Background)
710A165	284	SQFT	Class 10 Aluminum Flat Sign Panels 0.08" Thick (Type XI Background, Fluorescent)
710A170	151	SQFT	Class 4, Aluminum Flat Sign Panels 0.08" Thick (Type IV Background)
710B021	672	LF	Roadway Sign Post (#3 U Channel, Galvanized Steel or 2", 14 Ga Square Tubular Steel)
740B000	371	SQFT	Construction Signs
740E000	50	Each	Cones (36 Inches High)
740M001	50	Each	Ballast For Cone