

**Alabama Department of Transportation
Proposal Item Summary**

032. STPAA-0027(521)

DALE COUNTY

Contract Time: 90 Working Days

DBE Goal Percent: 1.00

for constructing the Micro-Milling, Resurfacing, Bridge Guardrail Retrofit, and Traffic Stripe on SR-27 from 0.320 mile west of the Ozark City Limits to the Henry County Line. Length 15.951 mi.

The Bracket Estimate on this project is from \$4,735,815 to \$5,788,219.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$6.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206D001	200	LF	Removing Guardrail
206E008	16	Each	Removing Guardrail End Anchor (All Type)
209A000	20	Each	Mailbox Reset, Single
210D021	100	CUYD	Borrow Excavation (Loose Truckbed Measurement)(A4 or Better)
212A000	1,668	STA	Machine Grading Shoulders
405A000	28,665	Gal	Tack Coat
408B001	273,000	SQYD	Micro-Milling Existing Pavement (Approximately 1.10" Thru 2.00" Thick)
410H000	1	Each	Material Remixing Device
424A341	30,031	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
424A350	1,054	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
424B640	100	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range A/B
424B700	100	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 3/8" Maximum Aggregate Size mix, ESAL Range A/B
428A001	32	Mile	Scoring Bituminous Pavement Surface
430B043	100	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
629D005	8	Each	Bridge Guardrail Retrofit, Type 13 (MASH)
630A001	100	LF	Steel Beam Guardrail, Class A, Type 2
630C079	8	Each	Guardrail End Anchor, Type 13 (MASH)
630C080	8	Each	Guardrail End Anchor, Type 20 Series (MASH)
650A000	2,060	CUYD	Topsoil
652A100	12	Acre	Seeding
652C000	48	Acre	Mowing
656A010	12	Acre	Mulching
659C002	300	SQYD	Erosion Control Product, Type S2
665A000	36	Acre	Temporary Seeding
665B001	24	Ton	Temporary Mulching
665J002	250	LF	Silt Fence
665O001	250	LF	Silt Fence Removal
665Q002	500	LF	Wattle
666A001	4	Acre	Pest Control Treatment
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 277,000.00)
701A227	33	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	25	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	6	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	170	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	12	Mile	Broken Temporary Traffic Stripe

Item No.	Quantity	Units	Description
701C001	114	Mile	Solid Temporary Traffic Stripe
701D007	1	Mile	Solid Traffic Stripe Removed (Paint)
701D008	1	Mile	Solid Traffic Stripe Removed (Plastic)
701D014	1	Mile	Broken Traffic Stripe Removed (Paint)
701D015	1	Mile	Broken Traffic Stripe Removed (Plastic)
701G146	1,654	LF	Solid White, Class W, Type A Traffic Stripe (5" Wide)
701G150	827	LF	Broken Yellow, Class W, Type A Traffic Stripe (5" Wide)
701G154	827	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
701G161	827	LF	Broken Black, Class W, Type B Traffic Stripe (5" Wide)
703A002	1,981	SQFT	Traffic Control Markings, Class 2, Type A
703B002	23	SQFT	Traffic Control Legends, Class 2, Type A
703D001	2,533	SQFT	Temporary Traffic Control Markings
705A030	103	Each	Pavement Markers, Class A-H, Type 2-C
705A032	325	Each	Pavement Markers, Class A-H, Type 1-B
705A037	1,472	Each	Pavement Markers, Class A-H, Type 2-D
705A038	57	Each	Pavement Markers, Class A-H, Type 2-E
705A039	64	Each	Pavement Markers, Class A-H, Type 2-A
740B000	2,871	SQFT	Construction Signs
740E000	150	Each	Cones (36 Inches High)
740M001	150	Each	Ballast For Cone
740O000	1	Each	Pilot Car
742A001	2	Each	Portable Changeable Message Sign, Type 2