

**Alabama Department of Transportation
Proposal Item Summary**

033. STPAA-0143(505)

ELMORE COUNTY

Contract Time: 40 Working Days

DBE Goal Percent: 1.00

for constructing the Planing, Resurfacing, and Traffic Stripe on SR-143 from the junction of Coosada Road to the junction of SR-14 in Millbrook. Length 2.670 mi.

The Bracket Estimate on this project is from \$1,191,691 to \$1,456,511.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$6.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
209A000	12	Each	Mailbox Reset, Single
209A001	1	Each	Mailbox Reset, Double
305B077	100	Ton	Crushed Aggregate, Section 825, For Miscellaneous Use
405A000	7,837	Gal	Tack Coat
408A052	74,641	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
410H000	1	Each	Material Remixing Device
424A360	6,520	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424A369	112	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B653	500	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B657	500	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
430B043	100	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
641S500	35	Each	Valve Box Reset
665G000	100	Each	Sand Bags
665J002	250	LF	Silt Fence
665O001	250	LF	Silt Fence Removal
665Q002	250	LF	Wattle
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 63,000.00)
701A227	7	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	6	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	1	Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701A244	4	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	3,523	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	8	Mile	Broken Temporary Traffic Stripe
701C001	21	Mile	Solid Temporary Traffic Stripe
703A002	7,127	SQFT	Traffic Control Markings, Class 2, Type A
703B002	1,286	SQFT	Traffic Control Legends, Class 2, Type A
703D001	8,768	SQFT	Temporary Traffic Control Markings
705A030	258	Each	Pavement Markers, Class A-H, Type 2-C
705A032	250	Each	Pavement Markers, Class A-H, Type 1-B
705A037	130	Each	Pavement Markers, Class A-H, Type 2-D
740B000	968	SQFT	Construction Signs
740C000	23	SQFT	Special Construction Signs
740D000	50	Each	Channelizing Drums
740E000	185	Each	Cones (36 Inches High)
740M001	185	Each	Ballast For Cone

Item No.	Quantity	Units	Description
7400000	1	Each	Pilot Car
741C010	2	Each	Portable Sequential Arrow And Chevron Sign Unit