

**Alabama Department of Transportation
Proposal Item Summary**

044. STPMN-2624(250)

ELMORE COUNTY

Contract Time: 35 Working Days

DBE Goal Percent: 2.00

for constructing the Widening, Resurfacing, and Traffic Stripe on CR-103 (Peace Church Road/Old Ware Road/Jackson Road) from the junction of Rifle Range Road to the junction of Redland Road. Length 5.499 mi.

The Bracket Estimate on this project is from \$1,397,055 to \$1,707,511.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$6.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206C010	57	SQYD	Removing Concrete Driveway
305B071	25	Ton	Coarse Aggregate, Section 801, For Miscellaneous Use
405A000	11,245	Gal	Tack Coat
408A052	95,700	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
424A346	9,300	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B640	150	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range A/B
424B647	708	Ton	Superpave Bituminous Concrete Upper Binder Layer, Widening, 1" Maximum Aggregate Size Mix, ESAL Range A/B
600A000	1	LS	Mobilization
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 74,000.00)
701A231	13	Mile	Solid White, Class 2, Type A Traffic Stripe
701A235	14	Mile	Solid Yellow, Class 2, Type A Traffic Stripe
701A245	3	Mile	Broken Yellow, Class 2, Type A Traffic Stripe
701B205	1,650	LF	Dotted, Class 2, Type A, Traffic Stripe
701C000	5	Mile	Broken Temporary Traffic Stripe
701C001	55	Mile	Solid Temporary Traffic Stripe
703A002	3,985	SQFT	Traffic Control Markings, Class 2, Type A
703B002	113	SQFT	Traffic Control Legends, Class 2, Type A
703D001	961	SQFT	Temporary Traffic Control Markings
703E001	113	SQFT	Temporary Traffic Control Legends
705A030	60	Each	Pavement Markers, Class A-H, Type 2-C
705A032	150	Each	Pavement Markers, Class A-H, Type 1-B
705A037	500	Each	Pavement Markers, Class A-H, Type 2-D
705A038	875	Each	Pavement Markers, Class A-H, Type 2-E
740B000	657	SQFT	Construction Signs
740E000	75	Each	Cones (36 Inches High)
740M001	75	Each	Ballast For Cone
740O000	1	Each	Pilot Car