

**Alabama Department of Transportation
Proposal Item Summary**

045. STPMN-5123(252)

MONTGOMERY COUNTY

Contract Time: 35 Working Days

for constructing the Planing, Resurfacing, and Traffic Stripe on CR-39 (Mount Zion Road) from the intersection of CR-70 (Paulk/Gibson Road) to the junction of CR-39 (Woodley Road) southeast of Montgomery. Length 6.291 mi.

The Bracket Estimate on this project is from \$869,547 to \$1,062,780.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$3.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
405A000	8,934	Gal	Tack Coat
408A052	486	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
424A346	7,147	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B640	100	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range A/B
430B043	1,662	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 46,000.00)
701A231	13	Mile	Solid White, Class 2, Type A Traffic Stripe
701A235	9	Mile	Solid Yellow, Class 2, Type A Traffic Stripe
701A245	4	Mile	Broken Yellow, Class 2, Type A Traffic Stripe
701C000	4	Mile	Broken Temporary Traffic Stripe
701C001	18	Mile	Solid Temporary Traffic Stripe
703A002	140	SQFT	Traffic Control Markings, Class 2, Type A
705A032	183	Each	Pavement Markers, Class A-H, Type 1-B
705A037	623	Each	Pavement Markers, Class A-H, Type 2-D
740B000	615	SQFT	Construction Signs
740O000	1	Each	Pilot Car