

**Alabama Department of Transportation
Proposal Item Summary**

004. HRRR-5523(250)

PIKE COUNTY

Contract Time: 30 Working Days

for constructing the Roadway Safety Improvements (Shoulder Widening, Flattening Slopes, and Traffic Stripe) on CR-7707 from the junction of CR-7718 to the junction of CR-7708. Length 3.649 mi.

The Bracket Estimate on this project is from \$369,867 to \$452,059.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$14.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
210A000	159	CUYD	Unclassified Excavation
210D021	4,841	CUYD	Borrow Excavation (Loose Truckbed Measurement)(A4 or Better)
405A000	165	Gal	Tack Coat
424B647	981	Ton	Superpave Bituminous Concrete Upper Binder Layer, Widening, 1" Maximum Aggregate Size Mix, ESAL Range A/B
600A000	1	LS	Mobilization
610D003	282	SQYD	Filter Blanket, Geotextile
650A000	2,437	CUYD	Topsoil
652A100	7	Acre	Seeding
656A010	7	Acre	Mulching
659C002	177	SQYD	Erosion Control Product, Type S2
665A000	7	Acre	Temporary Seeding
665J002	1,090	LF	Silt Fence
665O001	1,090	LF	Silt Fence Removal
665Q002	420	LF	Wattle
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 19,510.00)
701A227	8	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
740B000	357	SQFT	Construction Signs
740D000	50	Each	Channelizing Drums
740E000	200	Each	Cones (36 Inches High)
740M001	200	Each	Ballast For Cone
740O000	1	Each	Pilot Car