

**Alabama Department of Transportation
Proposal Item Summary**

017. NH-FMGR-0007(562)

JEFFERSON COUNTY

Contract Time: 30 Working Days

DBE Goal Percent: 2.00

for constructing the Resurfacing (Micro-Surfacing Seal Coat, Type II & Type III), Guardrail Installation, and Traffic Stripe on SR-7 (US-11) from the intersection of SR-75 in Roebuck to the I-459 Interchange. Length 2.862 mi.

The Bracket Estimate on this project is from \$909,214 to \$1,111,261.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$5.00 per set.

The Principal Items of work are approximately as follows:

| Item No. | Quantity | Units | Description |
|----------|----------|-------|---|
| 206D001 | 463 | LF | Removing Guardrail |
| 206E008 | 9 | Each | Removing Guardrail End Anchor (All Type) |
| 403B000 | 810 | Ton | Micro-Surfacing Seal Coat, Type II |
| 403B001 | 1,425 | Ton | Micro-Surfacing Seal Coat, Type III |
| 424B283 | 250 | Ton | Superpave Bituminous Concrete Upper Binder Layer, Patching, 1/2" Maximum Aggregate Size Mix, ESAL Range E |
| 600A000 | 1 | LS | Mobilization |
| 630A001 | 500 | LF | Steel Beam Guardrail, Class A, Type 2 |
| 630C077 | 4 | Each | Guardrail End Anchor, Type 8 (MASH) |
| 630C080 | 5 | Each | Guardrail End Anchor, Type 20 Series (MASH) |
| 698A000 | 1 | LS | Construction Fuel (Maximum Bid Limited to \$ 48,800.00) |
| 701A227 | 7 | Mile | Solid White, Class 2, Type A Traffic Stripe (5" Wide) |
| 701A230 | 6 | Mile | Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide) |
| 701A239 | 6 | Mile | Broken White, Class 2, Type A Traffic Stripe (5" Wide) |
| 701A244 | 2 | Mile | Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide) |
| 701B207 | 5,286 | LF | Dotted, Class 2, Type A Traffic Stripe (5" Wide) |
| 701C000 | 14 | Mile | Broken Temporary Traffic Stripe |
| 701C001 | 26 | Mile | Solid Temporary Traffic Stripe |
| 703A002 | 7,174 | SQFT | Traffic Control Markings, Class 2, Type A |
| 703B002 | 2,241 | SQFT | Traffic Control Legends, Class 2, Type A |
| 703D001 | 4,200 | SQFT | Temporary Traffic Control Markings |
| 705A030 | 1,150 | Each | Pavement Markers, Class A-H, Type 2-C |
| 705A032 | 100 | Each | Pavement Markers, Class A-H, Type 1-B |
| 705A037 | 150 | Each | Pavement Markers, Class A-H, Type 2-D |
| 740B000 | 802 | SQFT | Construction Signs |
| 740C000 | 12 | SQFT | Special Construction Signs |
| 740D000 | 350 | Each | Channelizing Drums |
| 741C010 | 2 | Each | Portable Sequential Arrow And Chevron Sign Unit |