

**Alabama Department of Transportation
Proposal Item Summary**

024. STPAA-0134(513)

DALE COUNTY

Contract Time: 40 Working Days

DBE Goal Percent: 3.00

for constructing the Micro-Milling, Resurfacing, and Traffic Stripe on SR-134 from the junction of CR-67 in Midland City to the Henry County Line. Length 4.735 mi.

The Bracket Estimate on this project is from \$1,615,786 to \$1,974,849.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$6.00 per set.

The Principal Items of work are approximately as follows:

| Item No. | Quantity | Units | Description |
|----------|----------|-------|--|
| 206D001 | 63 | LF | Removing Guardrail |
| 206E008 | 4 | Each | Removing Guardrail End Anchor (All Type) |
| 209A000 | 7 | Each | Mailbox Reset, Single |
| 212A000 | 500 | STA | Machine Grading Shoulders |
| 405A000 | 8,600 | Gal | Tack Coat |
| 408B001 | 81,906 | SQYD | Micro-Milling Existing Pavement (Approximately 1.10" Thru 2.00" Thick) |
| 410H000 | 1 | Each | Material Remixing Device |
| 424A361 | 9,028 | Ton | Superpave Bituminous Concrete Wearing Surface Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D |
| 424A370 | 324 | Ton | Superpave Bituminous Concrete Wearing Surface Layer, Widening, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D |
| 424B655 | 100 | Ton | Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D |
| 424B701 | 100 | Ton | Superpave Bituminous Concrete Upper Binder Layer, Leveling, 3/8" Maximum Aggregate Size mix, ESAL Range C/D |
| 428A001 | 10 | Mile | Scoring Bituminous Pavement Surface |
| 430B043 | 25 | Ton | Aggregate Surfacing (1" Down, Crusher Run) |
| 600A000 | 1 | LS | Mobilization |
| 630A001 | 25 | LF | Steel Beam Guardrail, Class A, Type 2 |
| 630C080 | 4 | Each | Guardrail End Anchor, Type 20 Series (MASH) |
| 650A000 | 1,851 | CUYD | Topsoil |
| 652A100 | 10 | Acre | Seeding |
| 652C000 | 47 | Acre | Mowing |
| 656A010 | 10 | Acre | Mulching |
| 665A000 | 19 | Acre | Temporary Seeding |
| 665B001 | 28 | Ton | Temporary Mulching |
| 665J002 | 1,000 | LF | Silt Fence |
| 665O001 | 1,000 | LF | Silt Fence Removal |
| 665Q002 | 1,000 | LF | Wattle |
| 666A001 | 10 | Acre | Pest Control Treatment |
| 698A000 | 1 | LS | Construction Fuel (Maximum Bid Limited to \$ 9,200.00) |
| 701A227 | 10 | Mile | Solid White, Class 2, Type A Traffic Stripe (5" Wide) |
| 701A230 | 7 | Mile | Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide) |
| 701A244 | 3 | Mile | Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide) |
| 701B207 | 190 | LF | Dotted, Class 2, Type A Traffic Stripe (5" Wide) |
| 701C000 | 6 | Mile | Broken Temporary Traffic Stripe |
| 701C001 | 64 | Mile | Solid Temporary Traffic Stripe |
| 701D007 | 1 | Mile | Solid Traffic Stripe Removed (Paint) |
| 701D008 | 1 | Mile | Solid Traffic Stripe Removed (Plastic) |
| 701D014 | 1 | Mile | Broken Traffic Stripe Removed (Paint) |

| Item No. | Quantity | Units | Description |
|-----------------|-----------------|--------------|---|
| 701D015 | 1 | Mile | Broken Traffic Stripe Removed (Plastic) |
| 703A002 | 2,493 | SQFT | Traffic Control Markings, Class 2, Type A |
| 703B002 | 45 | SQFT | Traffic Control Legends, Class 2, Type A |
| 703D001 | 954 | SQFT | Temporary Traffic Control Markings |
| 705A030 | 15 | Each | Pavement Markers, Class A-H, Type 2-C |
| 705A032 | 488 | Each | Pavement Markers, Class A-H, Type 1-B |
| 705A037 | 263 | Each | Pavement Markers, Class A-H, Type 2-D |
| 705A038 | 244 | Each | Pavement Markers, Class A-H, Type 2-E |
| 740B000 | 1,107 | SQFT | Construction Signs |
| 740E000 | 150 | Each | Cones (36 Inches High) |
| 740M001 | 150 | Each | Ballast For Cone |
| 740O000 | 1 | Each | Pilot Car |