

**Alabama Department of Transportation  
Proposal Item Summary**

**025. STPAA-0179(504)**

**ETOWAH AND MARSHALL COUNTIES**

Contract Time: 60 Working Days

DBE Goal Percent: 6.00

for constructing the Micro-Milling, Resurfacing (Scrub Seal), Guardrail Installation, and Traffic Stripe on SR-179 from the junction of SR-74 (US-278) to the junction of SR-168 southwest of Boaz. Length 10.429 mi.

The Bracket Estimate on this project is from \$2,819,554 to \$3,446,122.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$5.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity Units	Description
206D001	1,688 LF	Removing Guardrail
206E005	20 Each	Removing Concrete Posts
206E008	32 Each	Removing Guardrail End Anchor (All Type)
405A000	17,206 Gal	Tack Coat
408B001	172,045 SQYD	Micro-Milling Existing Pavement (Approximately 1.10" Thru 2.00" Thick)
410H000	1 Each	Material Remixing Device
424A340	14,196 Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424A349	526 Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B640	1,000 Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range A/B
428A001	32 Mile	Scoring Bituminous Pavement Surface
430B043	5,889 Ton	Aggregate Surfacing (1" Down, Crusher Run)
433A000	159,093 SQYD	Scrub Seal
600A000	1 LS	Mobilization
630A001	1,838 LF	Steel Beam Guardrail, Class A, Type 2
630C003	8 Each	Guardrail End Anchor, Type 13
630C080	20 Each	Guardrail End Anchor, Type 20 Series (MASH)
630G003	160 LF	Steel Beam Guardrail for Culvert, Class A, Type 2, Case 3
665J002	1,000 LF	Silt Fence
665O001	1,000 LF	Silt Fence Removal
665Q002	1,000 LF	Wattle
698A000	1 LS	Construction Fuel (Maximum Bid Limited to \$ 150,675.00)
701A227	21 Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	14 Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	6 Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	125 LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	17 Mile	Broken Temporary Traffic Stripe
701C001	104 Mile	Solid Temporary Traffic Stripe
703A002	1,208 SQFT	Traffic Control Markings, Class 2, Type A
703B002	225 SQFT	Traffic Control Legends, Class 2, Type A
703D001	3,624 SQFT	Temporary Traffic Control Markings
705A030	6 Each	Pavement Markers, Class A-H, Type 2-C
705A032	249 Each	Pavement Markers, Class A-H, Type 1-B
705A037	1,035 Each	Pavement Markers, Class A-H, Type 2-D
740B000	2,480 SQFT	Construction Signs
740D000	200 Each	Channelizing Drums
740E000	200 Each	Cones (36 Inches High)
740M001	200 Each	Ballast For Cone

<b>Item No.</b>	<b>Quantity</b>	<b>Units</b>	<b>Description</b>
7400000	1	Each	Pilot Car
741C010	2	Each	Portable Sequential Arrow And Chevron Sign Unit